



WESTPORT OIL AND GAS COMPANY, L.P.

410 Seventeenth Street #2300 Denver Colorado 80202-4436
Telephone: 303 573 5404 Fax: 303 573 5609

February 1, 2002

Department of the Interior
Bureau of Land Management
2850 Youngfield Street
Lakewood, CO 80215-7093
Attention: Ms. Martha Maxwell

RE: BLM Bond CO-1203
BLM Nationwide Bond 158626364
Surety - Continental Casualty Company
Belco Energy Corporation merger into Westport Oil and Gas Company, Inc.
Conversion of Westport Oil and Gas Company, Inc., into Westport Oil and Gas Company, L.P.
Assumption Rider - Westport Oil and Gas Company, L.P.

Dear Ms. Maxwell:

Pursuant to our recent conversations, please find the following list of enclosures for the BLM's consideration and approval:

Two (2) Assumption Riders, fully executed originals.
Copies of Belco Energy Corporation merger into Westport Oil and Gas Company, Inc.
Copies of Westport Oil and Gas Company, Inc., conversion into Westport Oil and Gas Company, L.P.
List of all Federal/BIA/State Leases - Belco/Westport's leases - in all states.

Please inform us of any additional information needed to complete the change to Westport Oil and Gas Company, L.P., as operator of record.

I thank you for your assistance and cooperation in this matter. Please do not hesitate contacting the undersigned, should a question arise.

Sincerely,
Westport Oil and Gas Company, L.P.

Debby J. Black
Engineer Technician

Encl:



United States Department of the Interior **RECEIVED**

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155

FEB 22 2002

DIVISION OF
OIL, GAS AND MINING

In Reply Refer To:

3106

UTU-25566 et al

(UT-924)

FEB 21 2002

NOTICE

Westport Oil and Gas Company L.P. : Oil and Gas
410 Seventeenth Street, #2300 :
Denver Colorado 80215-7093 :

Name Change Recognized

Acceptable evidence has been received in this office concerning the name change of Westport Oil and Gas Company, Inc. into Westport Oil and Gas Company, L.P. with Westport Oil and Gas Company, L.P. being the surviving entity.


For our purposes, the name change is recognized effective December 31, 2001.

The oil and gas lease files identified have been noted as to the name change. The exhibit was compiled from a list of leases obtained from our computer program. We have not abstracted the lease files to determine if the entities affected by this name change hold an interest in the leases identified nor have we attempted to identify leases where the entities are the operator on the ground maintaining no vested recorded title or operating rights interests. We will be notifying the Minerals Management Service and all applicable Bureau of Land Management offices of the change by a copy of this notice. If additional documentation for changes of operator are required by our Field Offices, you will be contacted by them.

If you identify additional leases in which the entities maintain an interest, please contact this office and we will appropriately document those files with a copy of this Notice.

Due to the name change, the name of the principal/obligor on the bond is required to be changed from Westport Oil and Gas Company, Inc. to Westport Oil and Gas Company, L.P.. You may accomplish this either by consent of surety rider on the original bond or a rider to the original bond. The bonds are held in Colorado.

UTU-03405
UTU-20895
UTU-25566
UTU-43156
UTU-49518
UTU-49519
UTU-49522
UTU-49523



Robert Lopez
Chief, Branch of
Minerals Adjudication

cc: Moab Field Office
Vernal Field Office
MMS, Reference Data Branch, MS3130, PO Box 5860, Denver CO 80217
State of Utah, DOGM, Attn: Jim Thompson (Ste. 1210), Box 145801, SLC UT 84114
Teresa Thompson (UT-922)
Joe Incardine (UT-921)

memorandum

Branch of Real Estate Services
Uintah & Ouray Agency

Date: 5 December, 2002

Reply to:
Attn of: Supervisory Petroleum Engineer

Subject: Modification of Utah Division of Oil, Gas and Mining Regulations

To: Director, Utah Division of Oil, Gas and Mining Division: John Baza

We have been advised of changes occurring with the operation of your database for Change of Operator. You will be modifying your records to reflect Change of Operator once you have received all necessary documentation from the companies involved, and perhaps in advance of our Notice of Concurrence/Approval of Change of Operator where Indian leases are involved.


We have no objection.

With further comment to Rulemaking, I wish to comment concerning the provision of Exhibits for upcoming Hearings. I would like to see the Uintah & Ouray Agency, BIA, and the Ute Indian Tribe, Energy & Mineral Resources Department added to the list of those parties that receive advance Exhibits so as to allow us to have research time prior to Hearing dates. We will be able to provide a more informed recommendation to the Oil, Gas and Mining Board. It would be best if we would receive only those Exhibits that concern Indian lands, specifically on or adjacent to Indian lands. This may be a difficult situation to attain, as it is not always clear where 'on or adjacent' occurs.

I am aware that you have gone to extra effort to correct this matter already, and I fully appreciate it. My request is intended only to allow the addition of Uintah & Ouray Agency and Ute Indian Tribe to the official listing.

We appreciate your concern, and hope that these comments are timely enough for consideration in the revision process.

CC: Minerals & Mining Section of RES
Ute Energy & Mineral Resources Department: Executive Director
chronos



001

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☐
(highlight changes)

APPLICATION FOR PERMIT TO DRILL

1A. TYPE OF WORK: DRILL <input checked="" type="checkbox"/> REENTER <input type="checkbox"/> DEEPEN <input type="checkbox"/>		5. MINERAL LEASE NO: U-01197-A-ST ^{State}	6. SURFACE: ^{Federal} <i>State</i>
B. TYPE OF WELL: OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> OTHER _____ SINGLE ZONE <input checked="" type="checkbox"/> MULTIPLE ZONE <input type="checkbox"/>		7. IF INDIAN, ALLOTTEE OR TRIBE NAME:	
2. NAME OF OPERATOR: El Paso Production Oil & Gas Company		8. UNIT or CA AGREEMENT NAME: NATURAL BUTTES UNIT	
3. ADDRESS OF OPERATOR: P.O. Box 1148 CITY Vernal STATE UT ZIP 84078		9. WELL NAME and NUMBER: CIGE/296	
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 522' FNL & 1026' FWL AT PROPOSED PRODUCING ZONE: <i>4423734Y 39.95477</i> <i>635623X -109.41228</i>		10. FIELD AND POOL, OR WILDCAT: Natural Buttes	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: 28.2 Miles Northwest of Ouray, Utah		12. COUNTY: Uintah	13. STATE: UTAH
15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) 522'	16. NUMBER OF ACRES IN LEASE: 1674.49	17. NUMBER OF ACRES ASSIGNED TO THIS WELL: 40	
18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) Refer to Topo C	19. PROPOSED DEPTH: 7,400	20. BOND DESCRIPTION: 400JU0705	
21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.): 5182.9 GL	22. APPROXIMATE DATE WORK WILL START:	23. ESTIMATED DURATION: 10 Days	

24. PROPOSED CASING AND CEMENTING PROGRAM			
SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT	SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT
11 - 12 1/4	8 5/8 or 9 5/8	250	Refer to 10 pt program
7 7/8	4 1/2 or 5 1/2	7,400	Refer to 10 pt program

RECEIVED

JAN 13 2003

DIV. OF OIL, GAS & MINING

25. ATTACHMENTS	
VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:	
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER	<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN
<input type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER	<input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER

NAME (PLEASE PRINT) Cheryl Cameron TITLE Operations

SIGNATURE *Cheryl Cameron* DATE 1/9/2003

(This space for State use only)


API NUMBER ASSIGNED: 43-047-34858

APPROVAL:

T10S, R22E, S.L.B.&M.


EL PASO PRODUCTION OIL & GAS COMPANY

Well location, CIGE #296, located as shown in the NW 1/4 NW 1/4 of Section 14, T10S, R22E, S.L.B.&M. Uintah County, Utah. Utah.



BASIS OF ELEVATION

TWO WATER TRIANGULATION STATION LOCATED IN THE NW 1/4 OF SECTION 1, T10S, R21E, S.L.B.&M. TAKEN FROM THE BIG PACK MTN NE, QUADRANGLE, UTAH, UTAH COUNTY, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5238 FEET.



CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME, OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

REGISTERED LAND SURVEYOR
REGISTRATION NO. 161319
STATE OF UTAH

LEGEND:

- └─┘ = 90° SYMBOL
- = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.

BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.
(NAD 83)
LATITUDE = 39°57'17.22" (39.954783)
LONGITUDE = 109°24'46.69" (109.412969)

UINTAH ENGINEERING & LAND SURVEYING
85 SOUTH 200 EAST - VERNAL, UTAH 84078
(435) 789-1017

SCALE 1" = 1000'		DATE SURVEYED: 09-09-02	DATE DRAWN: 09-11-02
PARTY B.B. T.H. D.R.B.		REFERENCES G.L.O. PLAT	
WEATHER HOT	FILE EL PASO PRODUCTION OIL & GAS COMPANY		

WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 01/13/2003

API NO. ASSIGNED: 43-047-34858

WELL NAME: CIGE 296

OPERATOR: EL PASO PROD OIL & GAS (N1845)

CONTACT: CHREYL CAMERON

PHONE NUMBER: 435-781-7023

PROPOSED LOCATION:

NWNW 14 100S 220E

SURFACE: ~~0522~~ ³⁷¹ FNL ~~1215~~ ¹²¹⁵ FWL 1215 FWLBOTTOM: ~~0522~~ ³⁷¹ FNL ~~1215~~ ¹²¹⁵ FWL 1215 FWL

UINTAH

NATURAL BUTTES (630)

LEASE TYPE: 3 - State

LEASE NUMBER: U-01197-A-ST

SURFACE OWNER: 3 - State

PROPOSED FORMATION: MVRD

INSPECT LOCATN BY: / /

Tech Review	Initials	Date
Engineering	Dred	3/24/03
Geology		
Surface		

LATITUDE: 39.95517

LONGITUDE: 109.41161

RECEIVED AND/OR REVIEWED:

- ☒ Plat
☒ Bond: Fed[] Ind[] Sta[3] Fee[]
 (No. 400JU0705)
☒ Potash (Y/N)
☒ Oil Shale 190-5 (B) or 190-3 or 190-13
☒ Water Permit
 (No. 43-8496)
☒ RDCC Review (Y/N)
 (Date:)
☒ Fee Surf Agreement (Y/N)

LOCATION AND SITING:

R649-2-3.

Unit NATURAL BUTTES ☒

R649-3-2. General

Siting: 460 From Qtr/Qtr & 920' Between Wells

R649-3-3. Exception

☒ Drilling Unit

Board Cause No: 173-14

Eff Date: 12-2-99

Siting: 460' fr a boundary & uncomm. Tract

R649-3-11. Directional Drill

COMMENTS:

Need Photo (01-28-03)

STIPULATIONS:

- ① Oil shale
 ② Surface Casing Cement Stop
 ③ STATEMENT OF BASIS

ON-SITE PREDRILL EVALUATION
Division of Oil, Gas and Mining

OPERATOR: EL PASO PRODUCTION OIL & GAS COMPANY. (WESTPORT)
WELL NAME & NUMBER: CIGE 296
API NUMBER: 43-047-34858
LEASE: U-01197-A-ST **FIELD/UNIT:** NATURAL BUTTES
LOCATION: 1/4, 1/4 NW/NW **Sec:** 14 **TWP:** 10S **RNG:** 22E 1215' FWL 371' FNL
LEGAL WELL SITING: 460' from unit boundary and uncommitted tracts.
GPS COORD (UTM): 4423989N 12635644E **SURFACE OWNER:** STATE OF UTAH

PARTICIPANTS

DAVID W. HACKFORD, (DOGM), FLOYD BARTLETT, (DWR), CARROLL ESTES, CARROLL WILSON, CLAY EINERSON, (EL PASO). COLBY KAY, (UELS).

REGIONAL/LOCAL SETTING & TOPOGRAPHY

SITE IS IN AN AREA OF LOW ROLLING HILLS AND SHALLOW DRAWS DRAINING TO THE EAST TOWARD BITTER CREEK 0.3 MILES AWAY. THE RIM OF BITTER CREEK CANYON IS APPROX. 300' WEST OF SITE. THE SLOPE DROPS OFF SHARPLY AT THIS POINT.

SURFACE USE PLAN

CURRENT SURFACE USE: WILDLIFE AND LIVESTOCK GRAZING, HUNTING.

PROPOSED SURFACE DISTURBANCE: LOCATION WILL BE 325' BY 215'. ACCESS ROAD WILL BE 300'.

LOCATION OF EXISTING WELLS WITHIN A 1 MILE RADIUS: SEE ATTACHED MAP FROM GIS DATABASE.

LOCATION OF PRODUCTION FACILITIES AND PIPELINES: ALL PRODUCTION FACILITIES WILL BE ON LOCATION AND ADDED AFTER DRILLING WELL. PIPELINE WILL FOLLOW ACCESS ROAD.

SOURCE OF CONSTRUCTION MATERIAL: ALL CONSTRUCTION MATERIAL WILL BE BORROWED FROM SITE DURING CONSTRUCTION OF LOCATION.

ANCILLARY FACILITIES: NONE WILL BE REQUIRED.

WASTE MANAGEMENT PLAN:

DRILLED CUTTINGS WILL BE SETTLED INTO RESERVE PIT. LIQUIDS FROM PIT WILL BE ALLOWED TO EVAPORATE. FORMATION WATER WILL BE CONFINED TO STORAGE TANKS. SEWAGE FACILITIES, STORAGE AND DISPOSAL WILL BE HANDLED BY COMMERCIAL CONTRACTOR. TRASH WILL BE CONTAINED IN TRASH BASKETS AND HAULED TO AN APPROVED LAND FILL.

ENVIRONMENTAL PARAMETERS

AFFECTED FLOODPLAINS AND/OR WETLANDS: NONE

FLORA/FAUNA: SALTBRUSH, SHADSCALE, PRICKLEY PEAR, SPINEY HOPSAGE, BLACK SAGE: PRONGHORN, COYOTES, SONGBIRDS, RAPTORS, RODENTS, RABBITS.

SOIL TYPE AND CHARACTERISTICS: LIGHT BROWN SANDY CLAY.

EROSION/SEDIMENTATION/STABILITY: VERY LITTLE NATURAL EROSION.
SEDIMENTATION AND STABILITY ARE NOT A PROBLEM AND LOCATION CONSTRUCTION
SHOULDN'T CAUSE AN INCREASE IN STABILITY OR EROSION PROBLEMS.

PALEONTOLOGICAL POTENTIAL: NONE OBSERVED.

RESERVE PIT

CHARACTERISTICS: 140' BY 70' AND 10' DEEP.

LINER REQUIREMENTS (Site Ranking Form attached): A 12 MIL LINER WILL BE
REQUIRED FOR RESERVE PIT.

SURFACE RESTORATION/RECLAMATION PLAN

AS PER SITLA.

SURFACE AGREEMENT: AS PER SITLA.

CULTURAL RESOURCES/ARCHAEOLOGY: SITE WAS INSPECTED BY MONTGOMERY
ARCHEOLOGICAL CONSULTANTS. A REPORT OF THIS INVESTIGATION WILL BE PLACED ON
FILE.

OTHER OBSERVATIONS/COMMENTS

THIS PREDRILL INVESTIGATION WAS CONDUCTED ON A COLD, FROSTY DAY WITH
THREE INCHES OF SNOW COVER.

ATTACHMENTS

PHOTOS OF THIS SITE WERE TAKEN AND PLACED ON FILE.

DAVID W. HACKFORD
DOGM REPRESENTATIVE

1/28/03. 1:30 PM
DATE/TIME

**Evaluation Ranking Criteria and Ranking Score
For Reserve and Onsite Pit Liner Requirements**

<u>Site-Specific Factors</u>	<u>Ranking</u>	<u>Site Ranking</u>
Distance to Groundwater (feet)		
>200	0	
100 to 200	5	
75 to 100	10	
25 to 75	15	
<25 or recharge area	20	<u>5</u>
Distance to Surf. Water (feet)		
>1000	0	
300 to 1000	2	
200 to 300	10	
100 to 200	15	
< 100	20	<u>0</u>
Distance to Nearest Municipal Well (feet)		
>5280	0	
1320 to 5280	5	
500 to 1320	10	
<500	20	<u>0</u>
Distance to Other Wells (feet)		
>1320	0	
300 to 1320	10	
<300	20	<u>0</u>
Native Soil Type		
Low permeability	0	
Mod. permeability	10	
High permeability	20	<u>10</u>
Fluid Type		
Air/mist	0	
Fresh Water	5	
TDS >5000 and <10000	10	
TDS >10000 or Oil Base Mud Fluid	15	
containing significant levels of hazardous constituents	20	<u>5</u>
Drill Cuttings		
Normal Rock	0	
Salt or detrimental	10	<u>0</u>
Annual Precipitation (inches)		
<10	0	
10 to 20	5	
>20	10	<u>0</u>
Affected Populations		
<10	0	
10 to 30	6	
30 to 50	8	
>50	10	<u>0</u>
Presence of Nearby Utility Conduits		
Not Present	0	
Unknown	10	
Present	15	<u>0</u>

Final Score 20 (Level III Sensitivity)

Sensitivity Level I = 20 or more; total containment is required.

Sensitivity Level II = 15-19; lining is discretionary.

Sensitivity Level III = below 15; no specific lining is required.





UTAH DIVISION OF WATER RIGHTS
WATER RIGHT POINT OF DIVERSION PLOT CREATED MON, FEB 24, 2003, 2:08 PM
PLOT SHOWS LOCATION OF 1 POINTS OF DIVERSION

PLOT OF AN AREA WITH A RADIUS OF 10000 FEET FROM A POINT
FEET, FEET OF THE CT CORNER,
SECTION 14 TOWNSHIP 10S RANGE 22E SL BASE AND MERIDIAN

PLOT SCALE IS APPROXIMATELY 1 INCH = 4000 FEET

N O R T H

**

**

**

**

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*

*


*

*

*

*

0



UTAH DIVISION OF WATER RIGHTS
NWPLAT POINT OF DIVERSION LOCATION PROGRAM

MAP CHAR	WATER RIGHT	QUANTITY CFS	AND/OR AC-FT	SOURCE DESCRIPTION or WELL INFO DIAMETER	DEPTH	YEAR LOG	POINT OF DIVERSION DESCRIPTION NORTH	EAST	CNR	SEC	TWN	RNG	B&
0	49 353	.4000	.00	7	1390		S 2128	E 2313	NW 12	10S	22E	S	
WATER USE(S): MINING				OTHER				PRIORITY DATE: 07/10/1					
Tosco Corporation				10100 Santa Monica Blvd				Los Angeles					



United States Department of the Interior

BUREAU OF INDIAN AFFAIRS

Washington, D.C. 20240

FEB 10 2003

IN REPLY REFER TO:
Real Estate Services

Carroll A. Wilson
Principal Landman
Westport Oil and Gas Company, L.P.
1368 South 1200 East
Vernal, Utah 84078

Dear Mr. Wilson:

This is in response to your request for approval of RLI Insurance Company's Nationwide Oil and Gas Lease Bond No. RLB0005239 executed effective December 17, 2002, (\$150,000 coverage) with Westport Oil and Gas Company, L. P., as principal.

This bond is hereby approved as of the date of this correspondence and will be retained in the Bureau of Indian Affairs' Division of Real Estate Services, 1849 C Street, NW, MS-4512-MIB, Washington, D.C. 20240. All Bureau oil and gas regional offices and the surety are being informed of this action.

In cases where you have existing individual and/or collective bonds on file with one or more of our regional offices, you may now request those offices, directly, to terminate in lieu of coverage under this Nationwide Bond.

Enclosed is a copy of the approved bond for your files. If we may be of further assistance in this matter, please advise.

Sincerely,

ACTING

Director, Office of Trust Responsibilities

Enclosure

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

003

SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells. Use APPLICATION FOR PERMIT -- for such proposals		6. Lease Designation and Serial Number U-01197-A-ST
		7. Indian Allottee or Tribe Name
		8. Unit or Communitization Agreement NATURAL BUTTES UNIT
1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other (specify)		9. Well Name and Number CIGE 296
2. Name of Operator El Paso Production Oil & Gas Company		10. API Well Number Not Assigned
3. Address of Operator P.O. Box 1148 Vernal, UT 84078	4. Telephone Number (435) 781-7023	11. Field and Pool, or Wildcat Natural Buttes
5. Location of Well Footage : 371' FNL & 1215' FWL (Re-Survey) 4423780 Y QQ, Sec. T., R., M : NWNW Sec. 14, T10S, R22E 635680 X 39.95517 - 109.41161 County : Uintah State : UT		

12. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA																											
<p style="text-align: center;">NOTICE OF INTENT (Submit in Duplicate)</p> <table style="width: 100%;"> <tr> <td><input type="checkbox"/> Abandonment</td> <td><input type="checkbox"/> New Construction</td> </tr> <tr> <td><input type="checkbox"/> Casing Repair</td> <td><input type="checkbox"/> Pull or Alter Casing</td> </tr> <tr> <td><input checked="" type="checkbox"/> Change of Plans</td> <td><input type="checkbox"/> Recompletion</td> </tr> <tr> <td><input type="checkbox"/> Conversion to Injection</td> <td><input type="checkbox"/> Shoot or Acidize</td> </tr> <tr> <td><input type="checkbox"/> Fracture Treat</td> <td><input type="checkbox"/> Vent or Flare</td> </tr> <tr> <td><input type="checkbox"/> Multiple Completion</td> <td><input type="checkbox"/> Water Shut-Off</td> </tr> <tr> <td colspan="2"><input type="checkbox"/> Other _____</td> </tr> </table> <p>Approximate Date Work Will Start _____</p>	<input type="checkbox"/> Abandonment	<input type="checkbox"/> New Construction	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Pull or Alter Casing	<input checked="" type="checkbox"/> Change of Plans	<input type="checkbox"/> Recompletion	<input type="checkbox"/> Conversion to Injection	<input type="checkbox"/> Shoot or Acidize	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Vent or Flare	<input type="checkbox"/> Multiple Completion	<input type="checkbox"/> Water Shut-Off	<input type="checkbox"/> Other _____		<p style="text-align: center;">SUBSEQUENT REPORT (Submit Original Form Only)</p> <table style="width: 100%;"> <tr> <td><input type="checkbox"/> Abandonment *</td> <td><input type="checkbox"/> New Construction</td> </tr> <tr> <td><input type="checkbox"/> Casing Repair</td> <td><input type="checkbox"/> Pull or Alter Casing</td> </tr> <tr> <td><input type="checkbox"/> Change of Plans</td> <td><input type="checkbox"/> Shoot or Acidize</td> </tr> <tr> <td><input type="checkbox"/> Conversion to Injection</td> <td><input type="checkbox"/> Vent or Flare</td> </tr> <tr> <td><input type="checkbox"/> Fracture Treat</td> <td><input type="checkbox"/> Water Shut-Off</td> </tr> <tr> <td colspan="2"><input type="checkbox"/> Other _____</td> </tr> </table> <p>Date of Work Completion _____</p> <p style="font-size: small;">Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION AND LOG form. * Must be accompanied by a cement verification report.</p>	<input type="checkbox"/> Abandonment *	<input type="checkbox"/> New Construction	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Pull or Alter Casing	<input type="checkbox"/> Change of Plans	<input type="checkbox"/> Shoot or Acidize	<input type="checkbox"/> Conversion to Injection	<input type="checkbox"/> Vent or Flare	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Water Shut-Off	<input type="checkbox"/> Other _____	
<input type="checkbox"/> Abandonment	<input type="checkbox"/> New Construction																										
<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Pull or Alter Casing																										
<input checked="" type="checkbox"/> Change of Plans	<input type="checkbox"/> Recompletion																										
<input type="checkbox"/> Conversion to Injection	<input type="checkbox"/> Shoot or Acidize																										
<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Vent or Flare																										
<input type="checkbox"/> Multiple Completion	<input type="checkbox"/> Water Shut-Off																										
<input type="checkbox"/> Other _____																											
<input type="checkbox"/> Abandonment *	<input type="checkbox"/> New Construction																										
<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Pull or Alter Casing																										
<input type="checkbox"/> Change of Plans	<input type="checkbox"/> Shoot or Acidize																										
<input type="checkbox"/> Conversion to Injection	<input type="checkbox"/> Vent or Flare																										
<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Water Shut-Off																										
<input type="checkbox"/> Other _____																											

13. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

It was determined during the on-site inspection on 1/28/03 that the location of the subject well should be moved away from the edge of Bitter Creek.

The footages have been changed from 522' FNL & 1026' FWL to 371' FNL & 1215' FWL, as reflected above.

Attached are 2 sets of amended plats, due to the re-survey.

RECEIVED
FEB 18 2003
 DIV. OF OIL, GAS & MINING


14. I hereby certify that the foregoing is true and correct.

Name & Signature Cheryl Cameron Title Operations Date 02/11/03
 (State Use Only)

T10S, R22E, S.L.B.&M.

EL PASO PRODUCTION OIL & GAS COMPANY

Well location, CIGE #296, located as shown in the NW 1/4 NW 1/4 of Section 14, T10S, R22E, S.L.B.&M. Uintah County, Utah. Utah.



LEGEND:


- └─┘ = 90° SYMBOL
- = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.

BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.
(NAD 83)
LATITUDE = 39°57'18.71" (39.955197)
LONGITUDE = 109°24'44.26" (109.412294)

BASIS OF ELEVATION

TWO WATER TRIANGULATION STATION LOCATED IN THE NW 1/4 OF SECTION 1, T10S, R21E, S.L.B.&M. TAKEN FROM THE BIG PACK MTN NE, QUADRANGLE, UTAH, UINTAH COUNTY, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5238 FEET.



CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

Robert H. Hays
REGISTERED LAND SURVEYOR
REGISTRATION NO. 161319
STATE OF UTAH

Revised: 01-30-03 D.R.B.

UINTAH ENGINEERING & LAND SURVEYING
85 SOUTH 200 EAST - VERNAL, UTAH 84078
(435) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 09-09-02	DATE DRAWN: 09-11-02
PARTY B.B. T.H. D.R.B.	REFERENCES G.L.O. PLAT	
WEATHER HOT	FILE EL PASO PRODUCTION OIL & GAS COMPANY	

**DIVISION OF OIL, GAS AND MINING
APPLICATION FOR PERMIT TO DRILL
STATEMENT OF BASIS**

OPERATOR: EL PASO PRODUCTION & GAS COMPANY. (WESTPORT)
WELL NAME & NUMBER: CIGE 296
API NUMBER: 43-047-34858
LOCATION: 1/4,1/4 NW/NW Sec:14 TWP: 10S RNG: 22E 1215' FWL 371' FNL

Geology/Ground Water:

El Paso proposes to set 250' of surface casing at this location. The depth to the base of the moderately saline water at this location is estimated to be at a depth of 4,700'. A search of Division of Water Rights records shows one water well within a 10,000 foot radius of the center of section 14 . This well is over a mile from the proposed location and is listed as a mining use well. The surface formation at this site is the Uinta Formation. The Uinta Formation is made up of interbedded shales and sandstones. The sandstones are mostly lenticular and discontinuous and should not be a significant source of useable ground water. Production casing cement should be brought to above the base of the moderately saline groundwater in order to isolate it from fresher waters uphole.

Reviewer: Brad Hill **Date:** 02/24/03

Surface:

The predrill investigation of the surface was performed on 1/28/03. Floyd Bartlett and Miles Hanberg with DWR and Ed Bonner with SITLA were invited to this investigation on 1/15/03. Mr. Bartlett was present. He did not have any concerns regarding the construction of this location or the drilling of the well. This site is on State surface. This site appears to be the best site for a location in the immediate area. Originally, this site was on the rim of Bitter Creek canyon. It was decided at this predrill investigation that the site should be moved approx. 300' to the northeast, and re-surveyed. Everyone at this investigation agreed to this. All information on this predrill form pertains to the new site.

Reviewer: David W. Hackford **Date:** 2/21/2003

Conditions of Approval/Application for Permit to Drill:

1. A synthetic liner with a minimum thickness of 12 mils shall be properly installed and maintained in the reserve pit.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

5. LEASE DESIGNATION AND SERIAL NUMBER:

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:

8. WELL NAME and NUMBER:
Exhibit "A"

9. API NUMBER:

10. FIELD AND POOL, OR WILDCAT:

1. TYPE OF WELL

OIL WELL ☐

GAS WELL ☐

OTHER _____

2. NAME OF OPERATOR:

El Paso Production Oil & Gas Company

3. ADDRESS OF OPERATOR:

9 Greenway Plaza

Houston

TX

77064-0995

PHONE NUMBER:

(832) 676-5933

4. LOCATION OF WELL

FOOTAGES AT SURFACE:

COUNTY:

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:

STATE:

UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

☐

NOTICE OF INTENT
(Submit in Duplicate)

Approximate date work will start:

☐

SUBSEQUENT REPORT
(Submit Original Form Only)

Date of work completion:

☐ ACIDIZE

☐ ALTER CASING

☐ CASING REPAIR

☐ CHANGE TO PREVIOUS PLANS

☐ CHANGE TUBING

☐ CHANGE WELL NAME

☐ CHANGE WELL STATUS

☐ COMMINGLE PRODUCING FORMATIONS

☐ CONVERT WELL TYPE

☐ DEEPEN

☐ FRACTURE TREAT

☐ NEW CONSTRUCTION

☒ OPERATOR CHANGE

☐ PLUG AND ABANDON

☐ PLUG BACK

☐ PRODUCTION (START/RESUME)

☐ RECLAMATION OF WELL SITE

☐ RECOMPLETE - DIFFERENT FORMATION

☐ REPERFORATE CURRENT FORMATION

☐ SIDETRACK TO REPAIR WELL

☐ TEMPORARILY ABANDON

☐ TUBING REPAIR

☐ VENT OR FLARE

☐ WATER DISPOSAL

☐ WATER SHUT-OFF

☐ OTHER: _____

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Operator change to Westport Oil and Gas Company, L.P., 1670 Broadway, Suite 2800, Denver, CO. 80202-4800, effective December 17, 2002.

BOND # _____

State Surety Bond No. RLB0005236
Fee Bond No. RLB0005238

EL PASO PRODUCTION OIL & GAS COMPANY

By: _____

Jon R. Nelsen, Attorney-in-Fact

RECEIVED

FEB 28 2003

DIV. OF OIL, GAS & MINING

WESTPORT OIL AND GAS COMPANY, L.P.

NAME (PLEASE PRINT)

David R. Dix

TITLE Agent and Attorney-in-Fact

SIGNATURE

DATE

12/17/02

(This space for State use only)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENTSUNDRY NOTICES AND REPORTS ON WELLS
*Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.*FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

5. Lease Serial No.

SEE ATTACHED EXHIBIT "A"

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

SEE ATTACHED EXHIBIT "A"

9. API Well No.

SEE ATTACHED EXHIBIT "A"

10. Field and Pool, or Exploratory Area

11. County or Parish, State

UINTAH COUNTY, UT

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

WESTPORT OIL & GAS COMPANY, L.P.

3a. Address

P.O. BOX 1148 VERNAL, UT 84078

3b. Phone No. (include area code)

(435) 781-7023

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SEE ATTACHED EXHIBIT "A"

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	SUCCESSOR OF
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	OPERATOR

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed when testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator determined that the site is ready for final inspection.

WESTPORT OIL & GAS COMPANY, L.P., IS CONSIDERED TO BE THE OPERATOR ON THE ATTACHED DESCRIBED LANDS AND IS RESPONSIBLE UNDER THE TERMS AND CONDITIONS OF THE LEASE FOR THE OPERATIONS CONDUCTED ON THE LEASED LANDS OR PORTIONS THEREOF, BOND COVERAGE FOR THIS WELL IS PROVIDED BY FEDERAL NATIONWIDE BOND NO. 158626364, EFFECTIVE FEBRUARY 1, 2002, AND BIA NATIONWIDE BOND NO. RLB0005239, EFFECTIVE FEBRUARY 10, 2003.

RECEIVED

MAR 04 2003

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

CHERYL CAMERON

Title

OPERATIONS

Date

March 4, 2003

BUREAU OF OIL, GAS & MINING

THIS SPACE FOR FEDERAL OR STATE USE

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)

Well name:	03-03 El Paso CIGE 296		
Operator:	El Paso Production Company		
String type:	Surface	Project ID:	43-047-34858
Location:	Uintah County		

Design parameters:
Collapse

Mud weight: 8.330 ppg
 Design is based on evacuated pipe.

Minimum design factors:
Collapse:

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
 Surface temperature: 65 °F
 Bottom hole temperature: 68 °F
 Temperature gradient: 1.40 °F/100ft
 Minimum section length: 200 ft

Cement top:

60 ft

** Surface Stop*

Burst

Max anticipated surface pressure: 0 psi
 Internal gradient: 0.468 psi/ft
 Calculated BHP 117 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
 8 Round LTC: 1.80 (J)
 Buttress: 1.60 (J)
 Premium: 1.50 (J)
 Body yield: 1.50 (B)

Tension is based on air weight.
 Neutral point: 219 ft

Non-directional string.

Re subsequent strings:

Next setting depth: 7,400 ft
 Next mud weight: 9.000 ppg
 Next setting BHP: 3,460 psi
 Fracture mud wt: 19.250 ppg
 Fracture depth: 250 ft
 Injection pressure 250 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	250	9.625	32.30	H-40	ST&C	250	250	8.876	15.8

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	108	1370	12.66	117	2270	19.42	8	254	31.46 J

Prepared by: Dustin Doucet
 Utah Dept. of Natural Resources

Phone: 801-538-5281
 FAX: 801-359-3940

Date: March 18, 2003
 Salt Lake City, Utah

ENGINEERING STIPULATIONS: Oil shale; Surface Casing Cemented to Surface

Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Collapse is based on a vertical depth of 250 ft, a mud weight of 8.33 ppg. The casing is considered to be evacuated for collapse purposes.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

Well name:

03-03 El Paso CIGE 296

Operator: El Paso Production Company

String type: Production

Project ID:

43-047-34858

Location: Uintah County

Design parameters:**Collapse**

Mud weight: 9.000 ppg

Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No

Surface temperature: 65 °F

Bottom hole temperature: 169 °F

Temperature gradient: 1.40 °F/100ft

Minimum section length: 368 ft

Cement top:

Surface**Burst**

Max anticipated surface pressure:

0 psi

Internal gradient: 0.466 psi/ft

Calculated BHP 3,460 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)

8 Round LTC: 1.80 (J)

Buttress: 1.60 (J)

Premium: 1.50 (J)

Body yield: 1.50 (B)

Non-directional string.

Tension is based on air weight.

Neutral point: 6,404 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	7400	4.5	11.60	J-55	LT&C	7400	7400	3.875	171.5
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	3460	4960	<u>1.43</u>	3460	5350	1.55	86	162	<u>1.89 J</u>

Prepared by: Dustin Doucet
Utah Dept. of Natural ResourcesPhone: 801-538-5281
FAX: 801-359-3940Date: March 18, 2003
Salt Lake City, Utah

ENGINEERING STIPULATIONS: Oil shale; Surface Casing Cemented to Surface


Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Collapse is based on a vertical depth of 7400 ft, a mud weight of 9 ppg. The casing is considered to be evacuated for collapse purposes.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

Casing Schematic



STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

004

SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells. Use APPLICATION FOR PERMIT -- for such proposals		6. Lease Designation and Serial Number U-01197-A-ST
		7. Indian Allottee or Tribe Name
		8. Unit or Communitization Agreement NATURAL BUTTES UNIT
		9. Well Name and Number CIGE 296
1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other (specify)		10. API Well Number
2. Name of Operator WESTPORT OIL & GAS COMPANY, L.P.		11. Field and Pool, or Wildcat NATURAL BUTTES
3. Address of Operator P.O. BOX 1148 VERNAL, UT 84078	4. Telephone Number (435) 781-7023	
5. Location of Well Footage : 522' FNL, 1026' FWL County : UINTAH QQ, Sec. T., R., M : NWNW SEC. 14, T10S, R223 State : UT		
12. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		

NOTICE OF INTENT
 (Submit in Duplicate)

- | | |
|--|---|
| <input type="checkbox"/> Abandonment | <input type="checkbox"/> New Construction |
| <input type="checkbox"/> Casing Repair | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans | <input type="checkbox"/> Recompletion |
| <input type="checkbox"/> Conversion to Injection | <input type="checkbox"/> Shoot or Acidize |
| <input type="checkbox"/> Fracture Treat | <input type="checkbox"/> Vent or Flare |
| <input type="checkbox"/> Multiple Completion | <input type="checkbox"/> Water Shut-Off |
| <input checked="" type="checkbox"/> Other <u>AMENDED DRLG PLAN</u> | |

Approximate Date Work Will Start _____

SUBSEQUENT REPORT
 (Submit Original Form Only)

- | | |
|--|---|
| <input type="checkbox"/> Abandonment * | <input type="checkbox"/> New Construction |
| <input type="checkbox"/> Casing Repair | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans | <input type="checkbox"/> Shoot or Acidize |
| <input type="checkbox"/> Conversion to Injection | <input type="checkbox"/> Vent or Flare |
| <input type="checkbox"/> Fracture Treat | <input type="checkbox"/> Water Shut-Off |
| <input type="checkbox"/> Other _____ | |

Date of Work Completion _____

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION AND LOG form.

* Must be accompanied by a cement verification report.

13. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

OPERATOR REQUESTS TO AMEND THE CURRENT DRLG PLAN AS SUBMITTED IN THE ORIGINAL APD.

REFER TO THE AMENDED DRILLIN PROGRAM FOR THE SUBJECT WELL.

Approved by the
Utah Division of
Oil, Gas and Mining

RECEIVED

MAR 18 2003

Date: 04-01-03

By: 

14. I hereby certify that the foregoing is true and correct.

Name & Signature CHERYL CAMERON Title OPERATIONS Date 03/10/03

(State Use Only)

Westport Oil and Gas Company, L.P.
DRILLING PROGRAM FOR APD

COMPANY NAME	Westport Oil & Gas Company, L.P.	DATE	March 10, 2003
WELL NAME	CIGE 296	TD	7,400' MD/TVD
FIELD	Natural Buttes	COUNTY	Uintah
		STATE	Utah
		ELEVATION	5,183' GL
SURFACE LOCATION	522 FNL, 1026 FWL, NWNW, SEC. 14, T10S, R22E	BHL	Straight Hole
OBJECTIVE ZONE(S)	Wasatch, Mesa Verde		
ADDITIONAL INFO	Regulatory Agencies: UDOGM, Tri-County Health Dept.		

GEOLOGICAL FORMATION			MECHANICAL		
LOGS	TOPS	DEPTH	HOLE SIZE	CASING SIZE	MUD WEIGHT
		20'		14"	
			12-1/4"	9-5/8", 32.3#, H-40, STC	Air mist
		250' MD/TVD			
Catch water sample if water is encountered from 250' to 4115					
	Green River @	1,100'			
No mud logging Cased hole logs only			7-7/8"	4-1/2", 11.6#, J-55, LTC	Air Mist/Polymer Aerated Water/Brine 8.3-9.0 ppg
	Wasatch @	4,115'			
	Mesa Verde @	6,500'			
		TD @ 7,400'			



Westport Oil and Gas Company, L.P.
DRILLING PROGRAM

CASING PROGRAM

	SIZE	INTERVAL	WT.	GR.	CPLG.	DESIGN FACTORS		
						BURST	COLLAPSE	TENSION
CONDUCTOR	14"	0-20'				2270	1370	254000
SURFACE	9-5/8"	0-250'	32.30	H-40	STC	16.19	11.71	4.37
						5350	4960	162000
PRODUCTION	4-1/2"	0-TD	11.60	J-55	LTC	2.05	1.43	1.19

- 1) Maximum Anticipated Surface Pressure (MASP) (Conductor and Surface Casings) = (Frac Gradient at Shoe - Gas Gradient (0.115 psi/ft))(TVD)
 2) MASP (Int Casing) = Pore Pressure at Next Casing Point - (Gas Gradient x TVD of Next Casing Point x 0.67) - (Mud Weight x TVD x 0.052 x 0.33)
 3) MASP (Prod Casing) = Pore Pressure - (Gas Gradient x TVD of Production Interval)
 (Burst Assumptions: FG @ 9-5/8" shoe = 13.0 ppg, Max Pore Pressure = 9.0 ppg EMW)
 (Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing, 50000 lbs overpull)

CEMENT PROGRAM

		FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE		250	Class G + 2% CaCl ₂ + 0.25 pps celloflake	110	35%	15.80	1.16
PRODUCTION	LEAD	3,610'	Premium Lite II + 3% KCl + 0.25 pps celloflake + 5 pps gilsonite + 10% gel + 0.5% extender	390	60%	11.00	3.38
	TAIL	3,790'	50/50 Poz/G + 10% salt + 2% gel	1060	60%	14.30	1.31

FLOAT EQUIPMENT & CENTRALIZERS

SURFACE	Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe.
PRODUCTION	Float shoe, 1 jt, float collar. Centralize first 3 joints & every third joint to top of tail cement with bow spring centralizers.

ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 3M with one annular and 2 rams. Test to 3,000 psi (annular to 1,500 psi) prior to drilling out. Record on chart recorder & tour sheet. Function test rams on each trip. Maintain safety valve & inside BOP on rig floor at all times. Kelly to be equipped with upper & lower kelly valves.

Drop Totco surveys on bit trips. Maximum allowable hole angle is 5 degrees.

Prepared By: Cheryl Cameron

DRILLING ENGINEER:

Dan Lindsey

DATE:

OPERATOR CHANGE WORKSHEET

007

ROUTING

1. GLH

2. CDW ✓

3. FILE

X Change of Operator (Well Sold)

Designation of Agent/Operator

Operator Name Change

Merger

The operator of the well(s) listed below has changed, effective: 12-17-02

FROM: (Old Operator):	TO: (New Operator):
EL PASO PRODUCTION OIL & GAS COMPANY	WESTPORT OIL & GAS COMPANY LP
Address: 9 GREENWAY PLAZA	Address: P O BOX 1148
HOUSTON, TX 77064-0995	VERNAL, UT 84078
Phone: 1-(832)-676-5933	Phone: 1-(435)-781-7023
Account No. N1845	Account No. N2115

CA No.

Unit:

WELL(S)

NAME	SEC TWN RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
SANTIO 4-233	04-09S-21E	43-047-34776	99999	INDIAN	GW	APD
CIGE 289	07-09S-21E	43-047-34865	99999	FEDERAL	GW	APD
NBU 452	08-09S-21E	43-047-34875	99999	FEDERAL	GW	APD
NBU 406	10-09S-21E	43-047-34747	99999	FEDERAL	GW	NEW
NBU 391	17-09S-21E	43-047-34874	99999	FEDERAL	GW	APD
NBU 410	32-09S-21E	43-047-34872	99999	STATE	GW	APD
CIGE 288	21-09S-21E	43-047-34842	99999	FEDERAL	GW	APD
NBU 445	30-09S-21E	43-047-34867	99999	FEDERAL	GW	APD
CIGE 225	03-10S-21E	43-047-34895	99999	FEDERAL	GW	APD
CIGE 291	10-10S-21E	43-047-34868	99999	FEDERAL	GW	APD
CIGE 290	10-10S-21E	43-047-34869	99999	FEDERAL	GW	APD
NBU 468	11-10S-21E	43-047-34856	99999	FEDERAL	GW	APD
CIGE 275	21-10S-21E	43-047-34799	99999	FEDERAL	GW	APD
CIGE 271	32-09S-22E	43-047-34795	99999	STATE	GW	APD
CIGE 293	08-10S-22E	43-047-34838	99999	FEDERAL	GW	APD
CIGE 294	08-10S-22E	43-047-34870	99999	FEDERAL	GW	APD
CIGE 292	08-10S-22E	43-047-34871	99999	FEDERAL	GW	APD
CIGE 298	09-10S-22E	43-047-34855	99999	FEDERAL	GW	APD
CIGE 297	14-10S-22E	43-047-34857	99999	STATE	GW	NEW
CIGE 296	14-10S-22E	43-047-34858	99999	STATE	GW	NEW
CIGE 299	14-10S-22E	43-047-34859	99999	FEDERAL	GW	APD

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

1. (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 02/28/2003
2. (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 03/04/2003
3. The new company has been checked through the **Department of Commerce, Division of Corporations Database** on: 03/06/2003
4. Is the new operator registered in the State of Utah: YES Business Number: 1355743-0181

5. If NO, the operator was contacted contacted on: _____

6. (R649-9-2)Waste Management Plan has been received on: IN PLACE

7. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM-12/31/2003 BIA-12/5/02

8. **Federal and Indian Units:**

The BLM or BIA has approved the successor of unit operator for wells listed on: 02/27/2003

9. **Federal and Indian Communization Agreements ("CA"):**

The BLM or BIA has approved the operator for all wells listed within a CA on: 01/09/2003

10. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: N/A

DATA ENTRY:

1. Changes entered in the **Oil and Gas Database** on: 03/28/2003

2. Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 03/28/2003

3. Bond information entered in RBDMS on: N/A

4. Fee wells attached to bond in RBDMS on: N/A

STATE WELL(S) BOND VERIFICATION:

1. State well(s) covered by Bond Number: RLB 0005236

FEDERAL WELL(S) BOND VERIFICATION:

1. Federal well(s) covered by Bond Number: 158626364

INDIAN WELL(S) BOND VERIFICATION:

1. Indian well(s) covered by Bond Number: RLB 0005239

FEE WELL(S) BOND VERIFICATION:

1. (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number RLB 0005238

2. The **FORMER** operator has requested a release of liability from their bond on: N/A
The Division sent response by letter on: N/A

LEASE INTEREST OWNER NOTIFICATION:

3. (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: N/A

COMMENTS:

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☒
(highlight changes)

APPLICATION FOR PERMIT TO DRILL		5. MINERAL LEASE NO: U-01187-A-ST	6. SURFACE: State
1A. TYPE OF WORK: DRILL <input checked="" type="checkbox"/> REENTER <input type="checkbox"/> DEEPEN <input type="checkbox"/>		7. IF INDIAN, ALLOTTEE OR TRIBE NAME:	
B. TYPE OF WELL: OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> OTHER _____ SINGLE ZONE <input checked="" type="checkbox"/> MULTIPLE ZONE <input type="checkbox"/>		8. UNIT or CA AGREEMENT NAME: NATURAL BUTTES UNIT	
2. NAME OF OPERATOR: El Paso Production Oil & Gas Company Westport Oil & Gas Co.		9. WELL NAME and NUMBER: CIGE 296	
3. ADDRESS OF OPERATOR: P.O. Box 1148 CITY Vernal STATE UT ZIP 84078		10. FIELD AND POOL, OR WILDCAT: Natural Buttes	
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 371' FNL, 1215 FWL AT PROPOSED PRODUCING ZONE:		11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NWNW 14 10S 22E	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: 28.2 Miles Northwest of Ouray, Utah		12. COUNTY: Uintah	13. STATE: UTAH
15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) 522'	16. NUMBER OF ACRES IN LEASE: 1674.49	17. NUMBER OF ACRES ASSIGNED TO THIS WELL: 40	
18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) Refer to Topo C	19. PROPOSED DEPTH: 7,400	20. BOND DESCRIPTION: 400JU0705	
21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.): 5182.9 GL	22. APPROXIMATE DATE WORK WILL START:	23. ESTIMATED DURATION: 10 Days	

24. PROPOSED CASING AND CEMENTING PROGRAM			
SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT	SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT
11 - 12 1/4	8 5/8 or 9 5/8	250	Refer to 10 pt program
7 7/8	4 1/2 or 5 1/2	7,400	Refer to 10 pt program

25. ATTACHMENTS

VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:


<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER	<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN
<input type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER	<input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER

NAME (PLEASE PRINT) Cheryl Cameron TITLE Operations

SIGNATURE *Cheryl Cameron* DATE 1/9/2003

(This space for State use only)

API NUMBER ASSIGNED: 43-047-34858




RECEIVED
APR 08 2003
DIV. OF OIL, GAS & MINING

T10S, R22E, S.L.B.&M.


EL PASO PRODUCTION OIL & GAS COMPANY

Well location, CIGE #296, located as shown in the NW 1/4 NW 1/4 of Section 14, T10S, R22E, S.L.B.&M. Uintah County, Utah. Utah.



BASIS OF ELEVATION

TWO WATER TRIANGULATION STATION LOCATED IN THE NW 1/4 OF SECTION 1, T10S, R21E, S.L.B.&M. TAKEN FROM THE BIG PACK MTN NE, QUADRANGLE, UTAH, UINTAH COUNTY, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5238 FEET.



SCALE

CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

REGISTERED LAND SURVEYOR
REGISTRATION NO. 161319
STATE OF UTAH

Revised: 01-30-03 D.R.B.

LEGEND:

- └─┘ = 90° SYMBOL
- = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.

BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.

(NAD 83)

LATITUDE = 39°57'18.71" (39.955197)

LONGITUDE = 109°24'44.26" (109.412294)

UINTAH ENGINEERING & LAND SURVEYING

85 SOUTH 200 EAST - VERNAL, UTAH 84078

(435) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 09-09-02	DATE DRAWN: 09-11-02
PARTY B.B. T.H. D.R.B.	REFERENCES G.L.O. PLAT	
WEATHER HOT	FILE EL PASO PRODUCTION OIL & GAS COMPANY	

CIGE 296
NWNW Sec. 14, T10S, R22E
Uintah County, UT
U-01197-A-ST

EL PASO PRODUCTION COMPANY
DRILLING PROGRAM

1. Estimated Tops of Important Geologic Markers:

<u>Formation</u>	<u>Depth</u>
KB	5190'
Green River	1100'
Wasatch	4115'
Mesaverde	6525'
Total Depth	7400'

2. Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations:

<u>Substance</u>	<u>Formation</u>	<u>Depth</u>
	KB	5190'
	Green River	1100'
	Wasatch	4115'
Gas	Mesaverde	6525'
Water	N/A	
Other Minerals	N/A	

3. Pressure Control Equipment (Schematic Attached)

The BOP stack will consist of one 11" 3,000 psi annular BOP, one 11" 3,000 psi double ram, and one 11' drilling spool. The lower ram will contain pipe rams, and the upper ram will contain blind rams.

The choke and kill lines and the choke manifold will have a 3,000 psi minimum pressure rating.

The hydrill will be tested to 1,500 psi. The rams, choke manifold, kelly safety valves, drill string safety valves, and inside BOP will be tested to 3,000 psi.

4. **Proposed Casing Program:**

<u>Purpose</u>	<u>Depth</u>	<u>Hole Size</u>	<u>Casing Size</u>	<u>Wt/ft</u>	<u>Grade</u>	<u>Type</u>
Surface	0-250'	11" or 12 1/4"	8 5/8" or 9 5/8"	24#, 32.3#, 36#, or 40#	K-55, H-40, or J-55	ST&C
Production	0-TD	7 7/8"	4 1/2" or 5 1/2"	11.6#	N-80	LT&C

The proposed casing and cementing program shall be conducted as approved to protect and/or isolate all usable water zones potentially productive zones, lost circulation zones, abnormally pressured zones, and any prospectively valuable deposits of minerals. Any isolating medium other than cement shall receive approval prior to use. The casing setting depth shall be calculated to position the casing seat opposite a competent formation that will contain the maximum pressure to which it will be exposed during normal drilling operations. Determination of casing setting depth shall be based on all relevant factors, including: presence/absence of hydrocarbons, fracture gradients, usable water zones, formation pressures, lost circulation zones, other minerals, or other unusual characteristics.

All casing, except conductor casing, shall be new or reconditioned and tested. Used casing shall meet or exceed API standards for new casing.

The surface casing shall be cemented back to surface either during the primary cement job or by remedial cementing. If drive pipe is used, it may be left in place if its total length is less than twenty feet below the surface. If the total length of the drive pipe is equal to or greater than twenty feet, it will be pulled prior to cementing surface casing, or it will be cemented in place.

As a minimum, usable water zones shall be isolated and/or protected by having a cement top for the production casing at least 200 feet above the base of the usable water. If gilsonite is encountered while drilling, it shall be isolated and/or protected via the cementing program.

Surface casing shall have centralizers on the bottom three joints, with a minimum of one centralizer per joint.

Top plugs shall be used to reduce contamination of cement by displacement fluid. A bottom plug or other acceptable technique, such as a suitable preflush fluid, inner string cement method, etc., shall be utilized to help isolate the cement from contamination by the mud being displaced ahead of the cement slurry.

Maximum anticipated bottom hole pressure calculated @ 7400' TD approximately equals 2960 psi (calculated at 0.4 psi/foot).

Maximum anticipated surface pressure equals approximately 1332 psi (bottomhole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot).

All casing strings below the conductor shall be pressure tested to 0.22 psi/foot of casing string length or to 1500 psi, whichever is greater, but not to exceed 70% of the minimum internal yield. If pressure declines more than 10% in 30 minutes, corrective action shall be taken.

Casing design is subject to revision based on geologic conditions encountered.

Proposed Cementing Program:

<u>Surface</u>	<u>Fill</u>	<u>Type & Amount</u>
0-250'	250'	A minimum of 85 sx Class "G" + 2% CaCl ₂ , 15.6 ppg, 1.19 cf/sx (Cement will be circulated to surface, about 25% excess)

<u>Production</u>	<u>Type & Amount</u>
200' above the top-most resource interval	Lead: Extended, Lite, or Hi-Fill cement + additives, 11 or 12 ppg, 2.69 cf/sx
TD-500' above productive internal	Tail: Extended Class "G" or 50:50 Poz + additives, 14 ppg, or RFC, 14.0 – 14.5 ppg, 1.57 cf/sx.

For production casing, actual cement volumes will be determined from the calculated hole volume + 60% excess, minimum. Cement volumes will include an amount sufficient to circulate to surface, if possible. Operator will continue to attempt to circulate cement to surface, but at a minimum, circulation will be 200' above the top of the Green River Formation, or as directed by the Authorized Officer (AO) or Acting, or as specified in the Conditions of Approval (COA) in the Application for Permit to Drill (APD).

For surface casing, waiting on cement time will be adequate to achieve 500 psi compressive strength at the casing shoe prior to drilling out.

Anticipated cement tops will be reported as to depth, not the expected number of sacks of cement to be used. The Division of Oil, Gas, and Mining (DOGM) Office shall be notified, with sufficient lead time, in order to have a DOGM representative on location while running all casing strings and cementing.

After cementing the surface pipe and/or any intermediate strings, but before commencing any test, The casing string shall stand cemented until the cement has reached a compressive strength of at least 500 psi at the shoe. WOC time shall be recorded in the Driller's Log.

Auxiliary Well Control Equipment to Be Used:

Kelly Cock

A sub with a full opening (TIW) valve having threads compatible with drill string tubulars.

5. Drilling Fluids Program:

WASATCH

<u>Interval</u>	<u>Type</u>	<u>Mud Weight</u>
0-TD	Air/Air Mist/Aerated Water/Water (as hole conditions Warrant) Displace Hole to 10 ppg brine mud, prior to logging.	8.4 ppg or less

MESAVERDE

<u>Interval</u>	<u>Type</u>	<u>Mud Weight</u>
0-TD	Air/Air Mist/Aerated Water/Water (as hole conditions warrant) Depending on hole conditions, the hole will be displaced to either 10 ppg brine or drilling mud prior to logging. If hole conditions warrant, a mud system will be used.	8.4 ppg or less

No chromate additives will be used in the mud system prior to approval to ensure adequate protection of fresh water aquifers.

No chemicals subject to reporting under SARA Title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling, testing, or completing of this well.

6. Evaluation Program:

The Evaluation Program may change at the discretion of the well site geologist with approval by The Authorized Officer.

Cased Hole Logs Only

GR/Dipole Sonic/Neutron: TD-500' above the Wasatch Formation
(to surface at times)

Drill Stem Tests: As deemed necessary

Cores: As deemed necessary

When cement has not been circulated to surface, the cement top will be determined by Either a temperature survey or cement bond log. Should a temperature survey fail to Locate the cement top, a cement bond log shall be run.

Open Hole Logs

PEX: From TD - Surface

7. Abnormal Conditions:

No abnormal temperatures or pressures are anticipated. No hydrogen sulfide has been encountered or is known to exist from previous drilling in the area at this depth.

8. Variances:

Operator requests approval to perform drilling operations without an automatic igniter because drilling will be performed with an air/mist medium.

9. **Other Information:**

All loading lines will be placed inside the berm surrounding the tank battery.

10. **Anticipated Starting Dates & Notification of Operations:**

Anticipated commencement date shall be upon approval of the proposed APD.

Drilling Days: Approximately 10 days

Completion Days: Approximately 7 days

CIGE 296
NWNW Sec. 14, T10S, R22E
Uintah County, UT
U-01197-A-ST

MULTI-POINT SURFACE USE & OPERATIONS PLAN

1. Existing Roads:

Refer to Topo Map A for directions to the location.

Refer to Topo Maps A and B for location of access roads within a 2-mile radius.

Refer to the attached directions to the proposed location site.

Refer to Topo Maps A and B for location of access roads within a 2 mile radius.

Improvements to existing access roads shall be determined at the on-site inspection.

All existing roads will be maintained and kept in good repair during all drilling and completion operations associated with this well.

2. Planned Access Roads:

Refer to Topo Map B for the location of the proposed access road.

The upgraded and new portions of the access road will be crowned and ditched with a running surface of 18 feet and a maximum disturbed width of 30 feet, *unless modified at the on-site inspection*. Appropriate water control will be installed to control erosion.

Existence of pipelines; maximum grade; turnouts; major cut and fills, culverts, or bridges; gates, cattle guards, fence cuts, or modifications to existing facilities shall be determined at the on-site.

The access road was centerline flagged during time of staking.

Surfacing material may be necessary, depending upon weather conditions.

Surface disturbance and vehicular traffic will be limited to the approved location and approved access route. Any additional area needed will be approved in advance.

3. Location of Existing Wells Within a 1-Mile Radius:

Please refer to Topo Map C.

4. Location of Existing & Proposed Facilities:

The following guidelines will apply if the well is productive.

All production facilities will be located on the disturbed portion of the well pad and at a minimum of 25 feet from the toe of the back slope or the top of the fill slope.

A dike will be constructed completely around those production facilities which contain fluids (i.e., production tanks, produced water tanks, and/or heater/treater). These dikes will be constructed of compacted subsoil, be impervious, hold 100% of the capacity of the largest tank, and be independent of the back cut.

All permanent (on-site six months or longer) above the ground structures constructed or installed, including pumping units, will be painted a flat, non-reflective, earthtone color to match one of the standard environmental colors, as determined by the five state Rocky Mountain Inter-Agency Committee.

All facilities will be painted within six months of installation. Facilities required to comply with the Occupational Safety and Health Act (OSHA) will be excluded. The required color is Carlsbad Canyon (2.5Y 6/2).

Any necessary pits will be properly fenced to protect livestock and prevent wildlife entry.

Refer to Topo Map D for the proposed pipeline placement.

5. **Location and Type of Water Supply:**

Water for drilling purposes will be obtained from Dalbo Inc.'s underground well located in Ouray, Utah, Sec. 32, T4S, R3E, Water User Claim #43-8496, Application #53617.

Water will be hauled to location over the roads marked on Maps A and B.

No water well is to be drilled on this lease.

6. **Source of Construction Materials:**

Surface and subsoil materials in the immediate area will be utilized.

Any gravel will be obtained from a commercial source.

7. **Methods of Handling Waste Materials:**

Drill cuttings will be contained and buried in the reserve pit.

Drilling fluids, including salts and chemicals, will be contained in the reserve pit. Upon termination of drilling and completion operations, the liquid contents of the reserve pit will be removed and disposed of at an approved waste disposal facility within 120 days after drilling is terminated.

The reserve pit will be constructed on the location and will not be located within natural drainage, where a flood hazard exists or surface runoff will destroy or damage the pit walls. The reserve pit will be constructed so that it will not leak, break, or allow discharge of liquids. *The need for a reserve pit liner will be determined at the on-site inspection.*

If a plastic reinforced liner is used, it will be a minimum of 12 mil thick, with sufficient bedding used to cover any rocks. The liner will overlap the pit walls and be covered with dirt and/or rocks to hold it in place. No trash or scrap that could puncture the liner will be disposed of in the pit.

Any spills of oil, gas, salt water, or other noxious fluids will be immediately cleaned up and removed to an approved disposal site.

A chemical porta-toilet will be furnished with the drilling rig.

Garbage, trash, and other waste materials will be collected in a portable, self-contained, fully enclosed trash cage during operations. No trash will be burned on location.

All debris and other waste material not contained in the trash cage will be cleaned up and removed from the location immediately after removal of the drilling rig.

Any open pits will be fenced during the operations. The fencing will be maintained until such time as the pits are backfilled.

No chemicals subject to reporting under SARA Title III (hazardous materials) in an amount greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.

Any produced water from the proposed well will be contained in a water tank and will then be hauled by truck to one of the pre-approved disposal sites: RNI, Sec. 5, T9S, R22E, NBU #159, Sec. 35, T9S, R21E, Ace Oilfield, Sec. 2, T6S, R20E, MC&MC, Sec. 12, T6S, R19E.

8. **Ancillary Facilities:**

None are anticipated.

9. **Well Site Layout:** (See Location Layout Diagram)

The attached Location Layout Diagram describes drill pad cross-sections, cuts and fills, and locations of the mud tanks, reserve pit, flare pit, pipe racks, trailer parking, spoil dirt stockpile(s), and surface material stockpile(s). ***This section is subject to modification as a result of the on-site inspection.***

Please see the attached diagram to describe rig orientation, parking areas, and access roads.

If it is determined that a pit liner will be used at the on-site inspection, the reserve pit will be lined, and when the reserve pit is closed, the pit liner will be buried below plow depth.

All pits will be fenced according to the following minimum standards:

39 inch net wire will be used with at least one strand of barbed wire on top of the net wire. Barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence.

The net wire shall be no more than two inches above the ground. The barbed wire shall be three inches over the net wire. Total height of the fence shall be at least 42 inches.

Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times.

Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any 2 fence posts shall be no greater than 16 feet.

All wire shall be stretched, by using a stretching device, before it is attached to corner posts.

The reserve pit fencing will be on three sides during drilling operations, and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.

Location size may change prior to the drilling pad cross-sections, cuts and fills, and locations of the mud tanks, reserve pit, flare pit, pipe racks, trailer parking, spoil dirt stockpile (s), and surface material stockpile(s).

10. **Plans for Reclamation of the Surface:**

Producing Location:

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, materials, trash, and debris not required for production.

Immediately upon well completion, any hydrocarbons in the pit shall be removed in accordance with 43 CFR 3162.7-1.

If a plastic, nylon reinforced liner is used, it shall be torn and perforated before backfilling of the reserve pit.

Before any dirt work associated with location restoration takes place, the reserve pit shall be as dry as possible. All debris in it will be removed. Other waste and spoil materials will be disposed of immediately upon completion of operations.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximate natural contours. The reserve pit will be reclaimed within 90 days from the date of well completion, weather permitting.

To prevent surface water (s) from standing (ponding) on the reclaimed reserve pit area, final reclamation of the reserve pit will consist of "mounding" the surface three feet above surrounding ground surface to allow the reclaimed pit area to drain effectively.

Upon completion of backfilling, leveling, and recontouring, the stockpiled topsoil will be spread evenly over the reclaimed area(s).

Dry Hole/Abandoned Location:

Abandoned well sites, roads, and other disturbed areas will be restored as near as practical to their original condition. Where applicable, these conditions include the re-establishment of

irrigation systems, the re-establishment of appropriate soil conditions, and re-establishment of vegetation as specified.

All disturbed surfaces will be recontoured to the approximate natural contours, with reclamation of the well pad and access road to be performed as soon as practical after final abandonment. Reseeding operations will be performed after completion of other reclamation operations.

11. **Surface Ownership:**

State of Utah
Division of Oil, Gas & Mining
P.O Box 145801
Salt Lake City, UT 84114

12. **Other Information:**

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, the approved Plan of Operations, and any applicable Notice of Lessees. The Operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished to the field representative to ensure compliance.

The Operator will control noxious weeds along Rights-Of-Way for roads, pipelines, well sites, or other applicable facilities.

A Class III archaeological survey has been conducted. A copy of this report is attached.

This proposed location is not within 460 feet from the boundary of the Natural Buttes Unit, nor is it within 460 feet of any non-committed tract lying within the boundaries of the Unit.

13. Lessee's or Operators's Representative & Certification:

Cheryl Cameron
Regulatory Analyst
El Paso Production Company
P.O. Box 1148
Vernal, UT 84078
(435) 781-7023

Scott Palmer
Drilling Manager
El Paso Production Company
9 Greenway Plaza
Houston, TX 77046
(832) 676-3391


Certification: All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice to Lessees.

The Operator will be fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

El Paso Production Company is considered to be the operator of the subject well. El Paso Production Company agrees to be responsible under terms and conditions of the lease for the operations conducted upon leased lands.

Bond coverage pursuant to 43 CFR 3104 for lease activities is being provided by El Paso Production Company, State Bond No. 400JU0705.

I hereby certify that I, or persons under my supervision, have inspected the proposed drill site and access route, that I am familiar with the conditions that currently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and the work associated with the operations proposed herein will be performed by the Operator, its contractors, and subcontractors in conformity with this plan and the terms and conditions under which it is approved.


Cheryl Cameron

1/9/03

Date



Westport Oil and Gas Company, L.P.
DRILLING PROGRAM

CASING PROGRAM

	SIZE	INTERVAL	WT.	GR.	CPLG.	DESIGN FACTORS		
						BURST	COLLAPSE	TENSION
CONDUCTOR	14"	0-20'				2270	1370	254000
SURFACE	9-5/8"	0-250'	32.30	H-40	STC	16.19	11.71	4.37
						5350	4960	162000
PRODUCTION	4-1/2"	0-TD	11.60	J-55	LTC	2.05	1.43	1.19

- 1) Maximum Anticipated Surface Pressure (MASP) (Conductor and Surface Casings) = (Frac Gradient at Shoe - Gas Gradient (0.115 psi/ft))(TVD)
 2) MASP (Int Casing) = Pore Pressure at Next Casing Point - (Gas Gradient x TVD of Next Casing Point x 0.67) - (Mud Weight x TVD x 0.052 x 0.33)
 3) MASP (Prod Casing) = Pore Pressure - (Gas Gradient x TVD of Production Interval)
 (Burst Assumptions: FG @ 9-5/8" shoe = 13.0 ppg, Max Pore Pressure = 9.0 ppg EMW)
 (Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing, 50000 lbs overpull)

CEMENT PROGRAM

		FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE		250	Class G + 2% CaCl ₂ + 0.25 pps celloflake	110	35%	15.80	1.16
PRODUCTION	LEAD	3,610'	Premium Lite II + 3% KCl + 0.25 pps celloflake + 5 pps gilsonite + 10% gel + 0.5% extender	390	60%	11.00	3.38
	TAIL	3,790'	50/50 Poz/G + 10% salt + 2% gel	1060	60%	14.30	1.31

FLOAT EQUIPMENT & CENTRALIZERS

SURFACE	Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe.
PRODUCTION	Float shoe, 1 jt, float collar. Centralize first 3 joints & every third joint to top of tail cement with bow spring centralizers.

ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 3M with one annular and 2 rams. Test to 3,000 psi (annular to 1,500 psi) prior to drilling out. Record on chart recorder & tour sheet. Function test rams on each trip. Maintain safety valve & inside BOP on rig floor at all times. Kelly to be equipped with upper & lower kelly valves.

Drop Totco surveys on bit trips. Maximum allowable hole angle is 5 degrees.

Prepared By: Cheryl Cameron

DRILLING ENGINEER: _____

Dan Lindsey

DATE: _____

EL PASO PRODUCTION OIL & GAS COMPANY

CIGE #296

LOCATED IN UINTAH COUNTY, UTAH
SECTION 14, T10S, R22E, S.L.B.&M.



PHOTO: VIEW FROM CORNER #5 TO LOCATION STAKE

CAMERA ANGLE: NORTHWESTERLY



PHOTO: VIEW FROM BEGINNING OF PROPOSED ACCESS

CAMERA ANGLE: SOUTHERLY



- Since 1964 -

U E L S Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
435-789-1017 uels@uelsinc.com

LOCATION PHOTOS


9 **13** **02**
MONTH DAY YEAR

PHOTO

TAKEN BY: B.B.

DRAWN BY: P.M.

REVISED: 01-30-03



LEGEND:

○ PROPOSED LOCATION



EL PASO PRODUCTION OIL & GAS COMPANY

CIGE #296

SECTION 14, T10S, R22E, S.L.B.&M.

371' FNL 1215' FWL




Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC
MAP

9 13 02
MONTH DAY YEAR

SCALE: 1:100,000 DRAWN BY: P.M. REVISED: 01-30-03





LEGEND:

————— EXISTING ROAD
 - - - - - PROPOSED ACCESS ROAD



EL PASO PRODUCTION OIL & GAS COMPANY

CIGE #296
 SECTION 14, T10S, R22E, S.L.B.&M.
 371' FNL 1215' FWL




Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813


TOPOGRAPHIC
 MAP

9 13 02
 MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: P.M. REVISED: 01-30-03







APPROXIMATE TOTAL PIPELINE DISTANCE = 300' +/-

LEGEND:

- PROPOSED ACCESS ROAD
- EXISTING PIPELINE
- PROPOSED PIPELINE



EL PASO PRODUCTION OIL & GAS COMPANY

CIGE #296

SECTION 14, T10S, R22E, S.L.B.&M.

371' FNL 1215' FWL



Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC
MAP

9 13 02
MONTH DAY YEAR

SCALE: 1" = 1000'

DRAWN BY: P.M.

REVISED: 01-30-03

D
TOPO

EL PASO PRODUCTION OIL & GAS COMPANY


LOCATION LAYOUT FOR

CIGE #296

SECTION 14, T10S, R22E, S.L.B.&M.

371' FNL 1215' FWL


FIGURE #1



SCALE: 1" = 50'
DATE: 01-30-03
Drawn By: D.R.B.

NOTE:

Flare Pit is to be located
a min. of 100' from the
Well Head.



NOTES:

Elev. Ungraded Ground At Loc. Stake = 5201.2'

FINISHED GRADE ELEV. AT LOC. STAKE = 5198.4'

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017



EL PASO PRODUCTION OIL & GAS COMPANY

TYPICAL CROSS SECTIONS FOR

CIGE #296

SECTION 14, T10S, R22E, S.L.B.&M.

371' FNL 1215' FWL



DATE: 01-30-03
Drawn By: D.R.B.




FIGURE #2

APPROXIMATE YARDAGES



CUT	
(6") Topsoil Stripping	= 1,210 Cu. Yds.
Remaining Location	= 5,450 Cu. Yds.
TOTAL CUT	= 6,660 CU.YDS.
FILL	= 3,950 CU.YDS.

EXCESS MATERIAL AFTER 5% COMPACTION	= 2,500 Cu. Yds.
Topsoil & Pit Backfill (1/2 Pit Vol.)	= 2,500 Cu. Yds.
EXCESS UNBALANCE (After Rehabilitation)	= 0 Cu. Yds.

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017

3,000 PSI

EOB STACK



CIGE 296
NWNW Sec. 14, T10S, R22E
Uintah County, UT
U-01197-A-ST

EL PASO PRODUCTION COMPANY
DRILLING PROGRAM

1. Estimated Tops of Important Geologic Markers:

<u>Formation</u>	<u>Depth</u>
KB	5190'
Green River	1100'
Wasatch	4115'
Mesaverde	6525'
Total Depth	7400'

2. Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations:

<u>Substance</u>	<u>Formation</u>	<u>Depth</u>
	KB	5190'
	Green River	1100'
	Wasatch	4115'
Gas	Mesaverde	6525'
Water	N/A	
Other Minerals	N/A	

3. Pressure Control Equipment (Schematic Attached)

The BOP stack will consist of one 11" 3,000 psi annular BOP, one 11" 3,000 psi double ram, and one 11' drilling spool. The lower ram will contain pipe rams, and the upper ram will contain blind rams.

The choke and kill lines and the choke manifold will have a 3,000 psi minimum pressure rating.

The hydrill will be tested to 1,500 psi. The rams, choke manifold, kelly safety valves, drill string safety valves, and inside BOP will be tested to 3,000 psi.

4. **Proposed Casing Program:**

<u>Purpose</u>	<u>Depth</u>	<u>Hole Size</u>	<u>Casing Size</u>	<u>Wt/ft</u>	<u>Grade</u>	<u>Type</u>
Surface	0-250'	11" or 12 1/4"	8 5/8" or 9 5/8"	24#, 32.3#, 36#, or 40#	K-55, H-40, or J-55	ST&C
Production	0-TD	7 7/8"	4 1/2" or 5 1/2"	11.6#	N-80	LT&C

The proposed casing and cementing program shall be conducted as approved to protect and/or isolate all usable water zones potentially productive zones, lost circulation zones, abnormally pressured zones, and any prospectively valuable deposits of minerals. Any isolating medium other than cement shall receive approval prior to use. The casing setting depth shall be calculated to position the casing seat opposite a competent formation that will contain the maximum pressure to which it will be exposed during normal drilling operations. Determination of casing setting depth shall be based on all relevant factors, including: presence/absence of hydrocarbons, fracture gradients, usable water zones, formation pressures, lost circulation zones, other minerals, or other unusual characteristics.

All casing, except conductor casing, shall be new or reconditioned and tested. Used casing shall meet or exceed API standards for new casing.

The surface casing shall be cemented back to surface either during the primary cement job or by remedial cementing. If drive pipe is used, it may be left in place if its total length is less than twenty feet below the surface. If the total length of the drive pipe is equal to or greater than twenty feet, it will be pulled prior to cementing surface casing, or it will be cemented in place.

As a minimum, usable water zones shall be isolated and/or protected by having a cement top for the production casing at least 200 feet above the base of the usable water. If gilsonite is encountered while drilling, it shall be isolated and/or protected via the cementing program.

Surface casing shall have centralizers on the bottom three joints, with a minimum of one centralizer per joint.

Top plugs shall be used to reduce contamination of cement by displacement fluid. A bottom plug or other acceptable technique, such as a suitable preflush fluid, inner string cement method, etc., shall be utilized to help isolate the cement from contamination by the mud being displaced ahead of the cement slurry.

Maximum anticipated bottom hole pressure calculated @ 7400' TD approximately equals 2960 psi (calculated at 0.4 psi/foot).

Maximum anticipated surface pressure equals approximately 1332 psi (bottomhole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot).

All casing strings below the conductor shall be pressure tested to 0.22 psi/foot of casing string length or to 1500 psi, whichever is greater, but not to exceed 70% of the minimum internal yield. If pressure declines more than 10% in 30 minutes, corrective action shall be taken.

Casing design is subject to revision based on geologic conditions encountered.

Proposed Cementing Program:

<u>Surface</u>	<u>Fill</u>	<u>Type & Amount</u>
0-250'	250'	A minimum of 85 sx Class "G" + 2% CaCl ₂ , 15.6 ppg, 1.19 cf/sx (Cement will be circulated to surface, about 25% excess)

<u>Production</u>	<u>Type & Amount</u>
200' above the top-most resource interval	Lead: Extended, Lite, or Hi-Fill cement + additives, 11 or 12 ppg, 2.69 cf/sx
TD-500' above productive internal	Tail: Extended Class "G" or 50:50 Poz + additives, 14 ppg, or RFC, 14.0 – 14.5 ppg, 1.57 cf/sx.

For production casing, actual cement volumes will be determined from the calculated hole volume + 60% excess, minimum. Cement volumes will include an amount sufficient to circulate to surface, if possible. Operator will continue to attempt to circulate cement to surface, but at a minimum, circulation will be 200' above the top of the Green River Formation, or as directed by the Authorized Officer (AO) or Acting, or as specified in the Conditions of Approval (COA) in the Application for Permit to Drill (APD).

For surface casing, waiting on cement time will be adequate to achieve 500 psi compressive strength at the casing shoe prior to drilling out.

Anticipated cement tops will be reported as to depth, not the expected number of sacks of cement to be used. The Division of Oil, Gas, and Mining (DOGM) Office shall be notified, with sufficient lead time, in order to have a DOGM representative on location while running all casing strings and cementing.

After cementing the surface pipe and/or any intermediate strings, but before commencing any test, The casing string shall stand cemented until the cement has reached a compressive strength of at least 500 psi at the shoe. WOC time shall be recorded in the Driller's Log.

Auxiliary Well Control Equipment to Be Used:

Kelly Cock

A sub with a full opening (TIW) valve having threads compatible with drill string tubulars.

5. Drilling Fluids Program:**WASATCH**

<u>Interval</u>	<u>Type</u>	<u>Mud Weight</u>
0-TD	Air/Air Mist/Aerated Water/Water (as hole conditions Warrant) Displace Hole to 10 ppg brine mud, prior to logging.	8.4 ppg or less

MESAVERDE

<u>Interval</u>	<u>Type</u>	<u>Mud Weight</u>
0-TD	Air/Air Mist/Aerated Water/Water (as hole conditions warrant) Depending on hole conditions, the hole will be displaced to either 10 ppg brine or drilling mud prior to logging. If hole conditions warrant, a mud system will be used.	8.4 ppg or less

No chromate additives will be used in the mud system prior to approval to ensure adequate protection of fresh water aquifers.

No chemicals subject to reporting under SARA Title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling, testing, or completing of this well.

6. Evaluation Program:

The Evaluation Program may change at the discretion of the well site geologist with approval by The Authorized Officer.

Cased Hole Logs Only

GR/Dipole Sonic/Neutron:	TD-500' above the Wasatch Formation (to surface at times)
Drill Stem Tests:	As deemed necessary
Cores:	As deemed necessary

When cement has not been circulated to surface, the cement top will be determined by Either a temperature survey or cement bond log. Should a temperature survey fail to Locate the cement top, a cement bond log shall be run.

Open Hole Logs

PEX:	From TD - Surface
------	-------------------

7. Abnormal Conditions:

No abnormal temperatures or pressures are anticipated. No hydrogen sulfide has been encountered or is known to exist from previous drilling in the area at this depth.

8. Variances:

Operator requests approval to perform drilling operations without an automatic igniter because drilling will be performed with an air/mist medium.

9. **Other Information:**

All loading lines will be placed inside the berm surrounding the tank battery.

10. **Anticipated Starting Dates & Notification of Operations:**

Anticipated commencement date shall be upon approval of the proposed APD.

Drilling Days: Approximately 10 days

Completion Days: Approximately 7 days

CIGE 296
NWNW Sec. 14, T10S, R22E
Uintah County, UT
U-01197-A-ST

MULTI-POINT SURFACE USE & OPERATIONS PLAN

1. Existing Roads:

Refer to Topo Map A for directions to the location.

Refer to Topo Maps A and B for location of access roads within a 2-mile radius.

Refer to the attached directions to the proposed location site.

Refer to Topo Maps A and B for location of access roads within a 2 mile radius.

Improvements to existing access roads shall be determined at the on-site inspection.

All existing roads will be maintained and kept in good repair during all drilling and completion operations associated with this well.

2. Planned Access Roads:

Refer to Topo Map B for the location of the proposed access road.

The upgraded and new portions of the access road will be crowned and ditched with a running surface of 18 feet and a maximum disturbed width of 30 feet, *unless modified at the on-site inspection*. Appropriate water control will be installed to control erosion.

Existence of pipelines; maximum grade; turnouts; major cut and fills, culverts, or bridges; gates, cattle guards, fence cuts, or modifications to existing facilities shall be determined at the on-site.

The access road was centerline flagged during time of staking.

Surfacing material may be necessary, depending upon weather conditions.

Surface disturbance and vehicular traffic will be limited to the approved location and approved access route. Any additional area needed will be approved in advance.

3. Location of Existing Wells Within a 1-Mile Radius

Please refer to Topo Map C.

4. Location of Existing & Proposed Facilities

The following guidelines will apply if the well is productive.

All production facilities will be located on the disturbed portion of the well pad and at a minimum of 25 feet from the toe of the back slope or the top of the fill slope.

A dike will be constructed completely around those production facilities which contain fluids (i.e., production tanks, produced water tanks, and/or heater/treater). These dikes will be constructed of compacted subsoil, be impervious, hold 100% of the capacity of the largest tank, and be independent of the back cut.

All permanent (on-site six months or longer) above the ground structures constructed or installed, including pumping units, will be painted a flat, non-reflective, earthtone color to match one of the standard environmental colors, as determined by the five state Rocky Mountain Inter-Agency Committee.

All facilities will be painted within six months of installation. Facilities required to comply with the Occupational Safety and Health Act (OSHA) will be excluded. The required color is Carlsbad Canyon (2.5Y 6/2).

Any necessary pits will be properly fenced to protect livestock and prevent wildlife entry.

Refer to Topo Map D for the proposed pipeline placement.

5. Location and Type of Water Supply:

Water for drilling purposes will be obtained from Dalbo Inc.'s underground well located in Ouray, Utah, Sec. 32, T4S, R3E, Water User Claim #43-8496, Application #53617.

Water will be hauled to location over the roads marked on Maps A and B.

No water well is to be drilled on this lease.

6. Source of Construction Materials

Surface and subsoil materials in the immediate area will be utilized.

Any gravel will be obtained from a commercial source.

7. Methods of Handling Waste Materials

Drill cuttings will be contained and buried in the reserve pit.

Drilling fluids, including salts and chemicals, will be contained in the reserve pit. Upon termination of drilling and completion operations, the liquid contents of the reserve pit will be removed and disposed of at an approved waste disposal facility within 120 days after drilling is terminated.

The reserve pit will be constructed on the location and will not be located within natural drainage, where a flood hazard exists or surface runoff will destroy or damage the pit walls. The reserve pit will be constructed so that it will not leak, break, or allow discharge of liquids. *The need for a reserve pit liner will be determined at the on-site inspection.*

If a plastic reinforced liner is used, it will be a minimum of 12 mil thick, with sufficient bedding used to cover any rocks. The liner will overlap the pit walls and be covered with dirt and/or rocks to hold it in place. No trash or scrap that could puncture the liner will be disposed of in the pit.

Any spills of oil, gas, salt water, or other noxious fluids will be immediately cleaned up and removed to an approved disposal site.

A chemical porta-toilet will be furnished with the drilling rig.

Garbage, trash, and other waste materials will be collected in a portable, self-contained, fully enclosed trash cage during operations. No trash will be burned on location.

All debris and other waste material not contained in the trash cage will be cleaned up and removed from the location immediately after removal of the drilling rig.

Any open pits will be fenced during the operations. The fencing will be maintained until such time as the pits are backfilled.

No chemicals subject to reporting under SARA Title III (hazardous materials) in an amount greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.

Any produced water from the proposed well will be contained in a water tank and will then be hauled by truck to one of the pre-approved disposal sites: RNI, Sec. 5, T9S, R22E, NBU #159, Sec. 35, T9S, R21E, Ace Oilfield, Sec. 2, T6S, R20E, MC&MC, Sec. 12, T6S, R19E.

8. **Ancillary Facilities**

None are anticipated.

9. **Well Site Layout:** (See Location Layout Diagram)

The attached Location Layout Diagram describes drill pad cross-sections, cuts and fills, and locations of the mud tanks, reserve pit, flare pit, pipe racks, trailer parking, spoil dirt stockpile(s), and surface material stockpile(s). ***This section is subject to modification as a result of the on-site inspection.***

Please see the attached diagram to describe rig orientation, parking areas, and access roads.

If it is determined that a pit liner will be used at the on-site inspection, the reserve pit will be lined, and when the reserve pit is closed, the pit liner will be buried below plow depth.

All pits will be fenced according to the following minimum standards:

39 inch net wire will be used with at least one strand of barbed wire on top of the net wire. Barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence.

The net wire shall be no more than two inches above the ground. The barbed wire shall be three inches over the net wire. Total height of the fence shall be at least 42 inches.

Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times.

Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any 2 fence posts shall be no greater than 16 feet.

All wire shall be stretched, by using a stretching device, before it is attached to corner posts.

The reserve pit fencing will be on three sides during drilling operations, and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.

Location size may change prior to the drilling pad cross-sections, cuts and fills, and locations of the mud tanks, reserve pit, flare pit, pipe racks, trailer parking, spoil dirt stockpile (s), and surface material stockpile(s).

10. **Plans for Reclamation of the Surface:**

Producing Location:

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, materials, trash, and debris not required for production.

Immediately upon well completion, any hydrocarbons in the pit shall be removed in accordance with 43 CFR 3162.7-1.

If a plastic, nylon reinforced liner is used, it shall be torn and perforated before backfilling of the reserve pit.

Before any dirt work associated with location restoration takes place, the reserve pit shall be as dry as possible. All debris in it will be removed. Other waste and spoil materials will be disposed of immediately upon completion of operations.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximate natural contours. The reserve pit will be reclaimed within 90 days from the date of well completion, weather permitting.

To prevent surface water (s) from standing (ponding) on the reclaimed reserve pit area, final reclamation of the reserve pit will consist of "mounding" the surface three feet above surrounding ground surface to allow the reclaimed pit area to drain effectively.

Upon completion of backfilling, leveling, and recontouring, the stockpiled topsoil will be spread evenly over the reclaimed area(s).

Dry Hole/Abandoned Location:

Abandoned well sites, roads, and other disturbed areas will be restored as near as practical to their original condition. Where applicable, these conditions include the re-establishment of

irrigation systems, the re-establishment of appropriate soil conditions, and re-establishment of vegetation as specified.

All disturbed surfaces will be recontoured to the approximate natural contours, with reclamation of the well pad and access road to be performed as soon as practical after final abandonment. Reseeding operations will be performed after completion of other reclamation operations.

11. Surface Ownership:

State of Utah
Division of Oil, Gas & Mining
P.O Box 145801
Salt Lake City, UT 84114

12. Other Information:

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, the approved Plan of Operations, and any applicable Notice of Lessees. The Operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished to the field representative to ensure compliance.

The Operator will control noxious weeds along Rights-Of-Way for roads, pipelines, well sites, or other applicable facilities.

A Class III archaeological survey has been conducted. A copy of this report is attached.

This proposed location is not within 460 feet from the boundary of the Natural Buttes Unit, nor is it within 460 feet of any non-committed tract lying within the boundaries of the Unit.

13. Lessee's or Operators's Representative & Certification:

Cheryl Cameron
Regulatory Analyst
El Paso Production Company
P.O. Box 1148
Vernal, UT 84078
(435) 781-7023

Scott Palmer
Drilling Manager
El Paso Production Company
9 Greenway Plaza
Houston, TX 77046
(832) 676-3391


Certification: All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice to Lessees.

The Operator will be fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

El Paso Production Company is considered to be the operator of the subject well. El Paso Production Company agrees to be responsible under terms and conditions of the lease for the operations conducted upon leased lands.

Bond coverage pursuant to 43 CFR 3104 for lease activities is being provided by El Paso Production Company, State Bond No. 400JU0705.

I hereby certify that I, or persons under my supervision, have inspected the proposed drill site and access route, that I am familiar with the conditions that currently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and the work associated with the operations proposed herein will be performed by the Operator, its contractors, and subcontractors in conformity with this plan and the terms and conditions under which it is approved.


Cheryl Cameron

1/9/03

Date

EL PASO PRODUCTION OIL & GAS COMPANY

CIGE #296

SECTION 14, T10S, R22E, S.L.B.&M.

PROCEED IN A WESTERLY DIRECTION FROM VERNAL, UTAH ALONG U.S. HIGHWAY 40 APPROXIMATELY 14.0 MILES TO THE JUNCTION OF STATE HIGHWAY 88; EXIT LEFT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 17.0 MILES TO OURAY, UTAH; PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 11.5 MILES ON THE SEEP RIDGE ROAD TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY, THEN SOUTHEASTERLY DIRECTION APPROXIMATELY 12.0 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTH; TURN RIGHT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 0.6 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY DIRECTION APPROXIMATELY 1.4 MILES THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTH; TURN LEFT AND PROCEED IN A NORTHERLY DIRECTION APPROXIMATELY 2.5 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD THE WEST; TURN LEFT AND PROCEED IN A WESTERLY DIRECTION APPROXIMATELY 100' TO THE BEGINNING OF THE PROPOSED ACCESS ROAD TO THE SOUTH; FOLLOW ROAD FLAGS IN A SOUTHERLY, THEN WESTERLY DIRECTION APPROXIMATELY 0.15 MILES TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM VERNAL, UTAH TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 59.15 MILES.

TD

CULTURAL RESOURCE INVENTORY OF
EL PASO PRODUCTION'S
EIGHT WELL LOCATIONS IN NATURAL BUTTES
(T 10S, R 22E, SECTIONS 10, 11, 14, AND 15)
UINTAH COUNTY, UTAH

COPY
INTL *CE* DATE *9/9/02*

Keith R. Montgomery

Prepared For:

Bureau of Land Management
Vernal Field Office

and

State of Utah
School and Institutional
Trust Lands Administration

Prepared Under Contract With:

El Paso Production Oil and Gas Company
1368 South 1200 East
Vernal, Utah 84078

Prepared By:

Montgomery Archaeological Consultants
P.O. Box 147
Moab, Utah 84532

MOAC Report No. 02-124

September 4, 2002

United States Department of Interior (FLPMA)
Permit No. 02-UT-60122

State of Utah Antiquities Project (Survey)
Permit No. U-02-MQ-0502b,s

INTRODUCTION

A cultural resource inventory was conducted by Montgomery Archaeological Consultants (MOAC) in August 2002 for El Paso Production Oil and Gas Company's proposed eight well locations (CIGE #295, CIGE #296, CIGE #297, NBU #394, NBU #461, NBU #462, NBU #463, and NBU #464). The proposed well locations and associated access and pipeline corridors are situated in the Natural Buttes area, southeast of Ouray, Utah (Figure 1). The survey was implemented at the request of Mr. Carroll Estes, El Paso Production Oil and Gas Company, Vernal, Utah. The project is situated on land administered by the Bureau of Land Management (BLM), Vernal Field Office and on land administered by State of Utah School and Institutional Trust Lands Administration (SITLA).

The objective of the inventory was to locate, document, and evaluate any cultural resources within the project area in order to comply with Section 106 of 36 CFR 800, the National Historic Preservation Act of 1966 (as amended). Also, the inventory was implemented to attain compliance with a number of federal and state mandates, including the National Environmental and Policy Act of 1969, the Archaeological and Historic Conservation Act of 1972, the Archaeological Resources Protection Act of 1979, the American Indian Religious Freedom Act of 1978, and Utah State Antiquities Act of 1973 (amended 1990).

The fieldwork was performed on August 14-18, 2002 by Keith R. Montgomery, (Principal Investigator), assisted in the field by Roger Stash and Mark Bond. The project was initiated under the auspices of U.S.D.I. (FLPMA) Permit No. 02-UT-60122 and State of Utah Antiquities Permit (Survey) No. U-02-MQ-0502b,s issued to MOAC.

A file search was performed Roger Stash and Mark Bond at Bureau of Land Management, Vernal Field Office on August 14, 2002. This consultation indicated that a number of archaeological inventories have been completed near the project areas, all for oil and gas development. Archaeological-Environmental Research Corporation has completed several inventories for Coastal Oil and Gas Corporation, including an inventory in 1981 of the NBU #73 well location (Hauck 1981). Each of the inventories completed in the area resulted in a finding of no cultural resources. In 1986, Metcalf Archaeological Consultants conducted an inventory of well location NBU #79 documenting no cultural resources (Metcalf Archaeological Consultants 1986). Metcalf also completed inventories for a number of Coastal Oil and Gas Corporation well locations during 1991 under two project numbers (Scott 1991a, 1991b). No cultural resources were documented during the inventories. In 1992, Metcalf Archaeological Consultants conducted an inventory for one well location documenting no cultural resources (Truesdale 1992). Montgomery Archaeological Consultants (MOAC) conducted several inventories in the area in 1998, one of which is in the immediate project area of well location CIGE #295 (Montgomery 1998a, 1998b). No cultural resources were documented during these surveys. MOAC also completed an inventory near the current project area in 2001 for El Paso Production; the inventory resulted in no findings (Montgomery 2001). In summary, although a number of inventories have been conducted in the area, no cultural resources have been documented in the immediate project area.

DESCRIPTION OF PROJECT AREA

The eight proposed El Paso Production well locations, access and pipeline corridors are situated in the Natural Buttes Field, southeast of Ouray, Utah. The legal description is T 10S, R 22E, Sections 10, 11, 14, and 15 (Figure 1). The proposed well locations are designated: CIGE #295, CIGE #296, CIGE #297, NBU #394, NBU #461, NBU #462, NBU #463, and NBU #464 (Table 1). Well locations NBU #462, NBU #463, and NBU #464 are situated on public lands administered by the Bureau of Land Management, Vernal Field Office. Well locations NBU #394, NBU #461, CIGE #295, CIGE #296, and CIGE #297 are situated on lands administered by State and Institutional Trust Lands (SITLA).

Table 1. El Paso Production's Natural Butte Eight Well Locations

Well Location Designation	Legal Location	Location at Surface	Access/Pipeline	Cultural Resources
CIGE #295	T 10S, R 22E, Sec. 14	622' FNL 2422' FWL	Access/Pipeline 787'	None
CIGE #296	T 10S, R 22E, Sec. 14	308' FNL 613' FWL	Access/Pipeline 656'	None
CIGE #297	T 10S, R 22E, Sec. 14	2381' FNL 1169' FWL	Access 330' Pipeline 1640'	None
NBU #394	T 10S, R 22E, Secs. 11 and 14	935' FSL 1336' FEL	Access/Pipeline 1115'	None
NBU #461	T 10S, R 22E, Sec. 14	1800' FNL 2175' FEL	Access in 10 acre	None
NBU #462, Alt #2	T 10S, R 22E, Sec. 15	2077' FNL 1729' FWL	Access 262' Pipeline 525'	None
NBU #463	T 10S, R 22E, Secs. 10 and 15	20' FNL 2395' FEL	Access in 10 acre Pipeline 656'	None
NBU #464	T 10S, R 22E, Sec. 15	1246' FNL 2314' FWL	Access in 10 acre Pipeline 1837'	None

Environment

The study area lies within the Uinta Basin physiographic unit, a distinctly bowl-shaped geologic structure (Stokes 1986:231). The Uinta Basin ecosystem is within the Green River drainage, considered to be the northernmost extension of the Colorado Plateau. The geology is comprised of Tertiary age deposits which include Paleocene age deposits, and Eocene age fluvial and lacustrine sedimentary rocks. The Uinta Formation, which is predominate in the project area, occurs as eroded outcrops formed by fluvial deposited, stream laid interbedded sand and mud, and is known for its prolific paleontological localities. Specifically, the project area occurs on the east side of Cottonwood Wash on the valley floor which is interspersed by flat topped buttes and narrow steep-sided ridges. The area is heavily dissected and carved by ephemeral drainages. The surface geology consists of hard pan residual soil armored with shale and sandstone pebbles as well as some sand shadows. The elevation averages 5100 feet a.s.l. The project occurs within the Upper Sonoran Desert Shrub Association which includes shadscale, greasewood, mat saltbrush, snakeweed, rabbitbrush, prickly pear cactus, Indian ricegrass and non-native vegetation. Modern disturbances include grazing, roads, and oil/gas development.




Figure 1. Inventory Area of El Paso Production Oil and Gas Company's Eight Proposed Well Locations, Access Roads, and Pipelines. USGS 7.5' Archy Bench, Utah 1987. Scale 1:24000.

SURVEY METHODOLOGY

An intensive pedestrian survey was performed for this project which is considered 100% coverage. At each of the proposed well locations, a ten acre area centered on the center stake of the location was surveyed by the archaeologists walking parallel transects spaced no more than 10 m (30 ft) apart. The access and pipeline corridors were each 100 feet wide, surveyed by walking parallel transects along the staked centerline, spaced no more than 10 m (30 ft) apart. A 45m (150 foot) wide corridor was inspected when access/pipeline routes shared a corridor. Ground visibility was considered to be good. A total of 100.8 acres was inventoried, 37.5 acres of which occurs on BLM (Vernal Field Office) administered land, and 63.3 acres of which occurs on State of Utah School and Institutional Trust Land (SITLA).

RESULTS AND RECOMMENDATIONS

The inventory of the eight proposed El Paso Production Oil and Gas Company well locations resulted in the location of no archaeological resources. Based on the findings, a determination of "no historic properties affected" is recommended for this undertaking pursuant to Section 106, CFR 800.

REFERENCES CITED

Hauck, F.R.
1981

Cultural Resource Evaluation of El Paso Production's NBU #73 Well Location, Uintah County, UT. Archeological-Environmental Research Corp. Bountiful, UT. BLM #047-486. BLM Form on file at the BLM Vernal Field Office.

Cultural Resource Evaluation of El Paso Production's NBU #39 Well Location, Uintah County, UT. Archeological-Environmental Research Corp. Bountiful, UT. BLM #047-404. BLM Form on file at the BLM Vernal Field Office. NO DATE AVAILABLE

Cultural Resource Evaluation of El Paso Production's CIGE #54 Well Location, Uintah County, UT. Archeological-Environmental Research Corp. Bountiful, UT. BLM #047-391. BLM Form on file at the BLM Vernal Field Office. NO DATE AVAILABLE

Metcalf Archaeological Consultants
1986

Cultural Resource Inventory of El Paso Production's NBU #79 Well Location, Uintah County, Utah. Metcalf Archaeological Consultants. Project No. U-86-MM-577b. BLM Form on file at the BLM Vernal Field Office.

Montgomery, K.R.
1998a

Cultural Resource Inventory of Coastal Oil and Gas Corporation's CIGE 246, NBU 333, NBU 347, NBU 349, and NBU 350 Well Locations and Access Roads in Uintah County, Utah. Montgomery Archaeological Consultants, Moab, Utah. Project No. U-98-MQ-0631b,s. On file at the BLM Vernal Field Office.

1998b

Cultural Resource Inventory of Coastal Oil and Gas Corporation's CIGE 247, NBU 345, and NBU 348 Well Locations, Access Roads, and Pipeline, Uintah County, Utah. Montgomery Archaeological Consultants, Moab, Utah. Project No. U-98-MQ-0715b,s. On file at the BLM Vernal Field Office.

2001

Cultural Resource Inventory of El Paso Production's Five Well Locations and Three Pipelines, Uintah County, Utah. Montgomery Archaeological Consultants, Moab, Utah. Project No. U-01-MQ-0680b,s. On file at the BLM Vernal Field Office.

Scott, J. M.
1991a

Cultural Resource Inventory for Coastal Oil and Gas Corporation's Several Wells, Access Roads, and Pipelines, Uintah County, Utah. Metcalf Archaeological Consultants, Eagle, CO. Project No. U-91-MM-055b. Several BLM Forms for individual well locations with same project number on file at the BLM Vernal Field Office.

1991b

Cultural Resource Inventory for Coastal Oil and Gas Corporation's NBU #171 Well and Access Location, Uintah County, Utah. Metcalf Archaeological Consultants, Eagle, CO. Project No. U-91-MM-478b,s. On file at the BLM Vernal Field Office.

Stokes, W.L.
1986

Geology of Utah. Utah Museum of Natural History and Utah Geological and Mineral Survey, Salt Lake City.

Truesdale, J.A.
1992

Results of a Class III Cultural Resource Inventory for Coastal Oil and Gas Corporation's Proposed Well NBU #205 and Access, Uintah County, Utah. Metcalf Archaeological Consultants, Eagle, CO. Project No. U-92-MM-394b,s. On file at the BLM Vernal Field Office.

EL PASO PRODUCTION OIL & GAS COMPANY

CIGE #296

LOCATED IN UINTAH COUNTY, UTAH
SECTION 14, T10S, R22E, S.L.B.&M.




PHOTO: VIEW FROM CORNER #5 TO LOCATION STAKE

CAMERA ANGLE: SOUTHWESTERLY



PHOTO: VIEW FROM BEGINNING OF PROPOSED ACCESS

CAMERA ANGLE: SOUTHERLY



- Since 1964 -

**U
E
L
S**

Uintah Engineering & Land Surveying

85 South 200 East Vernal, Utah 84078
435-789-1017 uels@uelsinc.com

LOCATION PHOTOS

9 13 02
MONTH DAY YEAR

PHOTO

TAKEN BY: B.B.

DRAWN BY: P.M.

REVISED: 00-00-00

EL PASO PRODUCTION OIL & GAS COMPANY

CIGE #296

LOCATED IN UINTAH COUNTY, UTAH
SECTION 14, T10S, R22E, S.L.B.&M.




PHOTO: VIEW FROM CORNER #5 TO LOCATION STAKE

CAMERA ANGLE: NORTHWESTERLY



PHOTO: VIEW FROM BEGINNING OF PROPOSED ACCESS

CAMERA ANGLE: SOUTHERLY



- Since 1964 -

UELS Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
435-789-1017 uels@uelsinc.com

LOCATION PHOTOS

9
MONTH

13
DAY

02
YEAR

PHOTO

TAKEN BY: B.B.

DRAWN BY: P.M.

REVISED: 01-30-03

EL PASO PRODUCTION OIL & GAS COMPANY


LOCATION LAYOUT FOR

CIGE #296

SECTION 14, T10S, R22E, S.L.B.&M.

371' FNL 1215' FWL

FIGURE #1




SCALE: 1" = 50'

DATE: 01-30-03

Drawn By: D.R.B.

NOTE:

Flare Pit is to be located a min. of 100' from the Well Head.



NOTES:

Elev. Ungraded Ground At Loc. Stake = 5201.2'

FINISHED GRADE ELEV. AT LOC. STAKE = 5198.4'

UINTAH ENGINEERING & LAND SURVEYING

85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017



EL PASO PRODUCTION OIL & GAS COMPANY

TYPICAL CROSS SECTIONS FOR

CIGE #296

SECTION 14, T10S, R22E, S.L.B.&M.

371' FNL 1215' FWL



DATE: 01-30-03
Drawn By: D.R.B.





FIGURE #2

APPROXIMATE YARDAGES

CUT	
(6") Topsoil Stripping	= 1,210 Cu. Yds.
Remaining Location	= 5,450 Cu. Yds.
TOTAL CUT	= 6,660 CU.YDS.
FILL	= 3,950 CU.YDS.

EXCESS MATERIAL AFTER 5% COMPACTION	= 2,500 Cu. Yds.
Topsoil & Pit Backfill (1/2 Pit Vol.)	= 2,500 Cu. Yds.
EXCESS UNBALANCE (After Rehabilitation)	= 0 Cu. Yds.

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017



LEGEND:

○ PROPOSED LOCATION



EL PASO PRODUCTION OIL & GAS COMPANY

CIGE #296

SECTION 14, T10S, R22E, S.L.B.&M.

371' FNL 1215' FWL




Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC
MAP

9 13 02
MONTH DAY YEAR

SCALE: 1:100,000 DRAWN BY: P.M. REVISED: 01-30-03





LEGEND:

- EXISTING ROAD
 PROPOSED ACCESS ROAD



EL PASO PRODUCTION OIL & GAS COMPANY

CIGE #296

SECTION 14, T10S, R22E, S.L.B.&M.


371' FNL 1215' FWL

TOPOGRAPHIC
MAP

9 13 02
MONTH DAY YEAR

B
TOPO

SCALE: 1" = 2000'	DRAWN BY: P.M.	REVISED: 01-30-03
-------------------	----------------	-------------------



LEGEND:

- DISPOSAL WELLS
- PRODUCING WELLS
- SHUT IN WELLS
- WATER WELLS
- ABANDONED WELLS
- TEMPORARILY ABANDONED

EL PASO PRODUCTION OIL & GAS COMPANY


CIGE #296
SECTION 14, T10S, R22E, S.L.B.&M.
371' FNL 1215' FWL



Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC MAP
 SCALE: 1" = 2000' DRAWN BY: P.M. REVISED: 01-30-03





APPROXIMATE TOTAL PIPELINE DISTANCE = 300' +/-

LEGEND:

- PROPOSED ACCESS ROAD
- - - - EXISTING PIPELINE
- - - - PROPOSED PIPELINE



EL PASO PRODUCTION OIL & GAS COMPANY

CIGE #296

SECTION 14, T10S, R22E, S.L.B.&M.

371' FNL 1215' FWL



Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC
MAP



9 13 02
 MONTH DAY YEAR

SCALE: 1" = 1000' **DRAWN BY: P.M.** **REVISED: 01-30-03**

D
TOPO

3,000 PSI

EOP STACK





State of Utah
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

1594 West North Temple, Suite 1210

PO Box 145801

Salt Lake City, Utah 84114-5801

(801) 538-5340 telephone

(801) 359-3940 fax

(801) 538-7223 TTY

www.nr.utah.gov

Michael O. Leavitt
Governor

Robert L. Morgan
Executive Director

Lowell P. Braxton
Division Director

April 8, 2003

Westport Oil & Gas Company, LP
PO Box 1148
Vernal, UT 84078

Re: CIGE 296 Well, 371' FNL, 1215' FWL, NW NW, Sec. 14, T. 10 South, R. 22 East,
Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-34858.

Sincerely,

John R. Baza
Associate Director

pab
Enclosures

cc: Uintah County Assessor
SITLA
Bureau of Land Management, Vernal Field Office

Operator: Westport Oil & Gas Company, LP
Well Name & Number CIGE 296
API Number: 43-047-34858
Lease: U-01197-A-ST

Location: NW NW **Sec.** 14 **T.** 10 South **R.** 22 East

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for Permit to Drill.

2. Notification Requirements

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- 24 hours prior to cementing or testing casing
- 24 hours prior to testing blowout prevention equipment
- 24 hours prior to spudding the well
- within 24 hours of any emergency changes made to the approved drilling program
- prior to commencing operations to plug and abandon the well

The following are Division of Oil, Gas and Mining contacts and their work telephone numbers (please leave a voice mail message if the person is not available to take the call):

- Dan Jarvis at (801) 538-5338
- Carol Daniels at (801) 538-5284 (spud)

3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. Compliance with the State of Utah Antiquities Act forbids disturbance of archeological, historical, or paleontological remains. Should archeological, historical or paleontological remains be encountered during your operations, you are required to immediately suspend all operations and immediately inform the Trust Lands Administration and the Division of State History of the discovery of such remains.

5. In accordance with Order in Cause No. 190-5(b) dated October 28, 1982, the Operator shall comply with requirements of Rules R649-3-31 and R649-3-27 pertaining to Designated Oil Shale Areas. Additionally, the operator shall ensure that the surface and/or production casing is properly cemented over the entire oil shale interval as defined by Rule R649-3-31. The Operator shall report the actual depth the oil shale is encountered to the Division.

Page Two

Conditions of Approval API#43-047-34858

April 8, 2003

6. Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis. (Copy Attached)
7. Surface casing shall be cemented to the surface.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

008

SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells. Use APPLICATION FOR PERMIT -- for such proposals		6. Lease Designation and Serial Number U-01197-A-ST
		7. Indian Allottee or Tribe Name
		8. Unit or Communitization Agreement NATURAL BUTTES UNIT
1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other (specify)		9. Well Name and Number CIGE 296
2. Name of Operator Westport Oil & Gas Company, L.P.		10. API Well Number 43-047-34850 ⁸
3. Address of Operator P.O. Box 1148 Vernal, UT 84078	4. Telephone Number (435) 781-7023	11. Field and Pool, or Wildcat Natural Buttes
5. Location of Well Footage : 371' FNL, 1215' FWL County : Uintah QQ, Sec. T., R., M : NWNW Sec. 14, T10S, R22E State : UT		
12. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		

NOTICE OF INTENT

(Submit in Duplicate)

<input type="checkbox"/> Abandonment	<input type="checkbox"/> New Construction
<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Pull or Alter Casing
<input checked="" type="checkbox"/> Change of Plans	<input type="checkbox"/> Recompletion
<input type="checkbox"/> Conversion to Injection	<input type="checkbox"/> Shoot or Acidize
<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Vent or Flare
<input type="checkbox"/> Multiple Completion	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Other _____	

Approximate Date Work Will Start Upon Approval**SUBSEQUENT REPORT**

(Submit Original Form Only)

<input type="checkbox"/> Abandonment *	<input type="checkbox"/> New Construction
<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Pull or Alter Casing
<input type="checkbox"/> Change of Plans	<input type="checkbox"/> Shoot or Acidize
<input type="checkbox"/> Conversion to Injection	<input type="checkbox"/> Vent or Flare
<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Other _____	

Date of Work Completion _____

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION AND LOG form.

* Must be accompanied by a cement verification report.

13. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Operator requests to amend the current Drilling Program; surface casing amended to 800', and TD to 8500'. Please refer to the attached DHD reflecting the current amendments.

**Approved by the
 Utah Division of
 Oil, Gas and Mining**

Date: 05-27-03By: [Signature]

COPY SENT TO OPERATOR

Date: 5-28-03Initials: CTO**RECEIVED****MAY 20 2003**

DIV. OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct.

Name & Signature Cheryl Cameron Title Operations Date 05/12/03

(State Use Only)



Westport Oil and Gas Company, L.P.

CASING PROGRAM

						DESIGN FACTORS		
	SIZE	INTERVAL	WT.	GR.	CPLG.	BURST	COLLAPSE	TENSION
CONDUCTOR	14"	0-20'				2270	1370	254000
SURFACE	9-5/8"	0-800'	32.30	H-40	STC	5.06	3.66	3.35
						5350	4960	162000
PRODUCTION	4-1/2"	0-TD	11.60	J-55	LTC	1.78	1.25	1.09

- 1) Maximum Anticipated Surface Pressure (MASP) (Conductor and Surface Casings) = (Frac Gradient at Shoe - Gas Gradient (0.115 psi/ft))(TVD)
- 2) MASP (Int Casing) = Pore Pressure at Next Casing Point - (Gas Gradient x TVD of Next Casing Point x 0.67) - (Mud Weight x TVD x 0.052 x 0.33)
- 3) MASP (Prod Casing) = Pore Pressure - (Gas Gradient x TVD of Production Interval)
- (Burst Assumptions: FG @ 9-5/8" shoe = 13.0 ppg, Max Pore Pressure = 9.0 ppg EMW)
- (Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing, 50000 lbs overpull)

CEMENT PROGRAM

		FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE		800	Class G + 2% CaCl ₂ + 0.25 pps celloflake	310	35%	15.80	1.16
PRODUCTION	LEAD	3,610'	Premium Lite II + 3% KCl + 0.25 pps celloflake + 5 pps gilsonite + 10% gel + 0.5% extender	390	60%	11.00	3.38
	TAIL	4,890'	50/50 Poz/G + 10% salt + 2% gel	1370	60%	14.30	1.31

FLOAT EQUIPMENT & CENTRALIZERS

SURFACE	Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe.
PRODUCTION	Float shoe, 1 jt, float collar. Centralize first 3 joints & every third joint to top of tail cement with bow spring centralizers.

ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 3M with one annular and 2 rams. Test to 3,000 psi (annular to 1,500 psi) prior to drilling out. Record on chart recorder & tour sheet. Function test rams on each trip. Maintain safety valve & inside BOP on rig floor at all times. Kelly to be equipped with upper & lower kelly valves.

Drop Totco surveys on bit trips. Maximum allowable hole angle is 5 degrees.

DRILLING ENGINEER:

Brad Laney

DATE: _____

DRILLING SUPERINTENDENT:

Randy Bayne

DATE: _____

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an
abandoned well. Use Form 3160-3 (APD) for such proposals.

009

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

WESTPORT OIL & GAS COMPANY, L.P.

3a. Address

P.O. BOX 1148 VERNAL, UT 84078

3b. Phone No. (include area code)

(435) 781-

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

Multiple Wells - see attached

4304734858

10S 22E 14

5. Lease Serial No.

Multiple Wells - see attached

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

891008900A

8. Well Name and No.

Multiple Wells - see attached

9. API Well No.

Multiple Wells - see attached

10. Field and Pool, or Exploratory Area

Natural Buttes Unit

11. County or Parish, State

Uintah County, UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

Westport Oil & Gas requests a variance to Onshore Order No. 4, Part IIIC.a. requiring each sales tank be equipped with a pressure-vacuum thief hatch and/or vent line valve. The variance is requested as an economic analysis shows the value of the shrunk condensate will not payout the incremental cost of purchasing and maintaining the valve resulting in a loss of value over the producing life of the well.

The volume lost to shrinkage by dropping the tank pressure from 6 ozs. to 0 psig is shown to be 0.3% of the tank volume. This was determined by lab analysis of a representative sample from the field. The sample shrunk from 98.82% of original volume to 98.52% when the pressure was dropped. The average NBU well produces approximately 6 bbls condensate per month. The resulting shrinkage would amount to 0.56 bbls per month lost volume due to shrinkage. The value of the shrunk and lost condensate does not recoup or payout the cost of installing and maintaining the valves and other devices that hold the positive tank pressure. An economic run based on the loss and costs is attached. Westport Oil & gas requests approval of this variance in order to increase the value of the well to the operator and the mineral royalty owners.

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

J.T. Conley

Signature

J.T. Conley

COPY SENT TO OPERATOR

Date: 9-16-03

Initials: CHD

Title

Operations Manager

9-2-2003

SEP 10 2003

DIV. OF OIL, GAS & MINING

THIS SPACE FOR FEDERAL OR STATE USE

Approved by

Title

Accepted by the
Utah Division of
Oil, Gas and Mining

Date

Federal Approval of This
Action is Necessary

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Date: 9/16/03

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)

Westport Oil & Gas, L.P.

Project Economics Worksheet

Instructions:

Fill in blue boxes with before and after project data. The evaluation results are shown below and graphed automatically at the bottom of the page. This sheet is protected to prevent accidental alteration of the formulas. See JTC for changes. OPX entered as annual costs and/or as unit OPX costs for \$/BF and \$/MCF

Project Name:

Condensate Shrinkage Economics

Is this job a well pull or production rig job ??? ☐ N (Y or N)

	BEFORE \$/Year	AFTER \$/Year	DIFFERENCE \$/Year
Gross Oil Revenue	\$1,088	\$1,099	\$11
Gross Gas Revenue	\$0	\$0	\$0
NGL Revenue	\$0	\$0	\$0
PULING UNIT SERVICE			\$0
WIRELINE SERVICE			\$0
SUBSURF EQUIP REPAIRS			\$0
COMPANY LABOR			\$0
CONTRACT LABOR	\$0	\$200	\$200
CONTR SERVICE			\$0
LEASE FUEL GAS	\$0	\$0	\$0
UTILITIES - ELECTRICITY	\$0	\$0	\$0
CHEMICAL TREATING			\$0
MATERIAL & SUPPLY	\$0	\$150	\$150
WATER & HAULING			\$0
ADMINISTRATIVE COSTS			\$0
GAS PLANT PROCESSING			\$0
Totals	\$0	\$350	\$350

Increased OPX Per Year

Investment Breakdown:

	Cap/Exp Code	Cost, \$
Capital \$	820/830/840	\$1,200
Expense \$	830/860	\$0
Total \$		\$1,200

Oil Price	\$ 23.00	\$/BO
Gas Price	\$ 3.10	\$/MCF
Electric Cost	\$ -	\$/ HP / day
OPX/BF	\$ 2.00	\$/BF
OPX/MCF	\$ 0.62	\$/MCF

Production & OPX Detail:

	Before		After		Difference
Oil Production	0.192	BOPD	0.194	BOPD	0.002
Gas Production	0	MCFPD	0	MCFPD	0
Wtr Production	0	BWPD	0	BWPD	0
Horse Power		HP		HP	0
Fuel Gas Burned		MCFPD		MCFPD	0

Project Life:

Life = 20.0 Years
(Life no longer than 20 years)

Internal Rate of Return:

After Tax IROR = #DIV/0!

AT Cum Cashflow:

Operating Cashflow = (\$2,917) (Discounted @ 10%)

Payout Calculation:

Payout = $\frac{\text{Total Investment}}{\text{Sum(OPX + Incremental Revenue)}} = 1$

Payout occurs when total AT cashflow equals investment
See graph below, note years when cashflow reaches zero

Payout = NEVER Years or #VALUE! Days


Gross Reserves:

Oil Reserves = 6 BO
Gas Reserves = 0 MCF
Gas Equiv Reserves = 38 MCFE

Notes/Assumptions:

An average NBU well produces 0.192 Bcpd with no tank pressure. The production is increased to 0.194 Bcpd if 6 ozs of pressure are placed on the tank. The increased production does not payout the valve cost or the estimated annual maintenance costs.

Project: Condensate Shrinkage Economics



Westport Oil and Gas, Inc.

NBU/Ouray Field

RFL 2003-022

COMPARISON OF FLASH BACK PRESSURES

Calculated by Characterized Equation-of-State

Flash Conditions		Gas/Oil Ratio (scf/STbbl) (A)	Specific Gravity of Flashed Gas (Air=1.000)	Separator Volume Factor (B)	Separator Volume Percent (C)
psig	°F				

Calculated at Laboratory Flash Conditions

80	70			1.019	
0	122	30.4	0.993	1.033	101.37%
0	60	0.0	—	1.000	98.14%

Calculated Flash with Backpressure using Tuned EOS

80	70			1.015	
6.0 oz	65	24.6	0.777	1.003	98.82%
0	60	0.0	—	1.000	98.52%
80	70			1.015	
4.0 oz	65	24.7	0.778	1.003	98.82%
0	60	0.0	—	1.000	98.52%
80	70			1.015	
2.0 oz	65	24.7	0.779	1.003	98.82%
0	60	0.0	—	1.000	98.52%
80	70			1.015	
0	65	24.8	0.780	1.003	98.82%
0	60	0.0	—	1.000	98.52%

(A) Cubic Feet of gas at 14.696 psia and 60 °F per Barrel of Stock Tank Oil at 60 °F.

(B) Barrels of oil at indicated pressure and temperature per Barrel of Stock Tank Oil at 60 °F.

(C) Oil volume at indicated pressure and temperature as a percentage of original saturated oil volume.

Note: Bubblepoint of sample in original sample container was 80 psig at 70° F with 1 cc water

WELL	LEGALS	STFLEASENO	CANUMBER	APINO
CIGE 258	19-9-21 NWSE	UTU0591	891008900A	430473466700S1 ✓
CIGE 259	6-10-21 SWNE	UTU01791	891008900A	430473436700S1
CIGE 260	6-10-21 NENE	UTU01791	891008900A	430473436800S1
CIGE 261	7-10-21 NWSE	UTU02270A	891008900A	430473436900S1
CIGE 262	7-10-21 SENE	UTU01791	891008900A	430473437000S1
CIGE 263	19-10-22 SESE	ML20714	891008900A	430473422600S1
CIGE 264	19-10-21 SWSW	ML-22792	891008900A	430473422700S1
CIGE 265	15-9-20 SENE	UTU0144868	891008900A	430473478100S1
CIGE 266	33-9-22 NWSW	UTU01191A	891008900A	430473438600S1
CIGE 268	8-10-22 NWSE	UTU01196E	891008900A	430473441200S1
CIGE 271	32-9-22 SWNE	ML22649	891008900A	430473479500S1
CIGE 274	13-9-21 NENW	UTU01193	891008900A	430473477800S1
CIGE 275	21-10-21 NENW	UTU02278	891008900A	430473479900S1
CIGE 276	21-10-21 SWNW	UTU02278	891008900A	430473441700S1
CIGE 277	21-10-21 NWNW	UTU02278	891008900A	430473480000S1
CIGE 278	14-10-21 NESE	UTU01393C	891008900A	430473444500S1 ✓
CIGE 279	14-10-21 SESE	UTU01393C	891008900A	430473447900S1 ✓
CIGE 280	5-10-22 SWNW	UTU01195	891008900A	430473444300S1 ✓
CIGE 281	5-10-22 NWSW	UTU01191A	891008900A	430473444400S1 ✓
CIGE 282	7-10-22 NENE	ML23609	891008900A	430473443600S1 ✓
CIGE 283	35-9-21 SESE	ML22582	891008900A	430473479000S1 ✓
CIGE 284	1-10-21 SWNW	ML23612	891008900A	430473479200S1
CIGE 285	2-10-21 NENE	ML22652	891008900A	430473479300S1
CIGE 286	9-10-21 SENE	U01416	891008900A	430473479700S1
CIGE 287	9-10-21 NWSE	U01416	891008900A	430473479800S1
CIGE 288	21-9-21 NWSE	UTU0576	891008900A	430473486500S1 ✓
CIGE 289	7-9-21 NWSE	UTU0575B	891008900A	430473486900S1 ✓
CIGE 290	10-10-21 NESE	UTU0149079	891008900A	430473486800S1
CIGE 291	10-10-21 NWSE	UTU0149079	891008900A	430473486800S1
CIGE 292	8-10-22 SESE	UTU01196E	891008900A	430473487100S1
CIGE 293	8-10-22 SWSE	UTU01196E	891008900A	430473483800S1
CIGE 294	8-10-22 NENW	UTU466	891008900A	430473487000S1
CIGE 295	14-10-22 NENW	UTU01197A-ST	891008900A	430473482000S1
CIGE 296	14-10-22 NWNW	U01197A-ST	891008900A	430473485800S1 ✓
CIGE 297	14-10-22 SWNW	U01197A-ST	891008900A	430473485700S1 ✓
CIGE 298	9-10-22 SESW	UTU01196B	891008900A	430473485500S1
CIGE 299	14-10-22 NWSW	UTU468	891008900A	430473485900S1
NBU 004	23-9-21 NESE	UTU0149075	891008900A	430473005600S1
NBU 006	24-9-21 NWSE	UTU0149076	891008900A	430473008300S1
NBU 015	26-9-21 SESW	U99070-01	891008900A	430473020400S1
NBU 016	34-9-22 SWSE	UTU0149077	891008900A	430473020900S1
NBU 018	10-10-22 SWNE	UTU025187	891008900A	430473022100S1

010

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells. Use APPLICATION FOR PERMIT -- for such proposals		6. Lease Designation and Serial Number U-01197-A-ST
		7. Indian Allottee or Tribe Name
		8. Unit or Communitization Agreement NATURAL BUTTES UNIT
1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other (specify)		9. Well Name and Number CIGE 296
2. Name of Operator WESTPORT OIL & GAS COMPANY L.P.		10. API Well Number 43-047-34858
3. Address of Operator 1368 SOUTH 1200 EAST VERNAL, UTAH 84078	4. Telephone Number (435) 781-7024	11. Field and Pool, or Wildcat NATURAL BUTTES
5. Location of Well Footage : 371'FNL & 1215'FWL County : UINTAH QQ, Sec, T., R., M : NWNW SECTION 14-T10S-R-22E State : UTAH		
12. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		

NOTICE OF INTENT

(Submit in Duplicate)

<input type="checkbox"/> Abandonment	<input type="checkbox"/> New Construction
<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Pull or Alter Casing
<input type="checkbox"/> Change of Plans	<input type="checkbox"/> Recompletion
<input type="checkbox"/> Conversion to Injection	<input type="checkbox"/> Shoot or Acidize
<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Vent or Flare
<input type="checkbox"/> Multiple Completion	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Other <u>APD EXTENSION</u>	

Approximate Date Work Will Start IMMEDIATE**SUBSEQUENT REPORT**

(Submit Original Form Only)

<input type="checkbox"/> Abandonment *	<input type="checkbox"/> New Construction
<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Pull or Alter Casing
<input type="checkbox"/> Change of Plans	<input type="checkbox"/> Shoot or Acidize
<input type="checkbox"/> Conversion to Injection	<input type="checkbox"/> Vent or Flare
<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Other _____	

Date of Work Completion _____

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION AND LOG form.

* Must be accompanied by a cement verification report.

13. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

THE OPERATOR REQUESTS AUTHORIZATION FOR A ONE YEAR EXTENSION ON THE SUBJECT WELL LOCATION. IN ORDER TO COMPLETE DRILLING OPERATIONS.

Approved by the
Utah Division of
Oil, Gas and Mining

Date: 04-08-04
 By: [Signature]

COPY SENT TO OPERATOR
 Date: 4-12-04
 Initials: CHD

RECEIVED
APR 05 2004

DIV. OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct.

Name & Signature SHEILA UPCHEGO [Signature] Title Regulatory Analyst Date 03/22/04
 (State Use Only)

**Application for Permit to Drill
Request for Permit Extension
Validation**

(this form should accompany the Sundry Notice requesting permit extension)

API: 43-047-34858
Well Name: CIGE 296
Location: NWNW SECTION 14-T10S-R22E
Company Permit Issued to: WESTPORT OIL & GAS CO., L.P.
Date Original Permit Issued: 4/8/2003

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision.

Following is a checklist of some items related to the application, which should be verified.

If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes ☐ No ☒

Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes ☐ No ☒

Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes ☐ No ☒

Have there been any changes to the access route including ownership, or right-of-way, which could affect the proposed location? Yes ☐ No ☒

Has the approved source of water for drilling changed? Yes ☐ No ☒

Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes ☐ No ☒

Is bonding still in place, which covers this proposed well? Yes ☒ No ☐


Signature

3/22/2004

Date

Title: REGULATORY ANALYST

Representing: WESTPORT OIL & GAS CO., L.P.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

014

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells.
 Use APPLICATION FOR PERMIT -- for such proposals

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other (specify) _____		6. Lease Designation and Serial Number U-01197-A-ST
2. Name of Operator WESTPORT OIL & GAS COMPANY L.P.		7. Indian Allottee or Tribe Name
3. Address of Operator 1368 SOUTH 1200 EAST VERNAL, UTAH 84078		8. Unit or Communitization Agreement NATURAL BUTTES UNIT
4. Telephone Number (435) 781-7024		9. Well Name and Number CIGE 296
5. Location of Well Footage : 371'FNL & 1215'FWL QQ, Sec. T., R., M : NWNW SECTION 14-T10S-R-22E		10. API Well Number 43-047-34858
		11. Field and Pool, or Wildcat NATURAL BUTTES
12. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		

NOTICE OF INTENT

(Submit in Duplicate)

<input type="checkbox"/> Abandonment	<input type="checkbox"/> New Construction
<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Pull or Alter Casing
<input checked="" type="checkbox"/> Change of Plans	<input type="checkbox"/> Recompletion
<input type="checkbox"/> Conversion to Injection	<input type="checkbox"/> Shoot or Acidize
<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Vent or Flare
<input type="checkbox"/> Multiple Completion	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Other _____	

Approximate Date Work Will Start IMMEDIATE**SUBSEQUENT REPORT**

(Submit Original Form Only)

<input type="checkbox"/> Abandonment *	<input type="checkbox"/> New Construction
<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Pull or Alter Casing
<input type="checkbox"/> Change of Plans	<input type="checkbox"/> Shoot or Acidize
<input type="checkbox"/> Conversion to Injection	<input type="checkbox"/> Vent or Flare
<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Other _____	

Date of Work Completion _____

Report results of Multiple Completions and Recompletions to different reservoirs
 on WELL COMPLETION OR RECOMPLETION AND LOG form.

* Must be accompanied by a cement verification report.

13. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

THE OPERATOR REQUESTS AUTHORIZATION TO CHANGE THE SURFACE CASING FROM 800';
 TO SET A DEEPER SURFACE CASING TO 2,000'.

PLEASE REFER TO THE STANDARD OPERATING PROCEDURE (SOP) FOR CEMENTING AND CASING PROCEDURES.

RECEIVED**JUN 22 2004**

DIV. OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct.

Name & Signature SHEILA UPCHEGO Title Regulatory Analyst Date 06/09/04

(State Use Only)

**APPROVED BY THE STATE
 OF UTAH DIVISION OF
 OIL, GAS, AND MINING**

DATE: 7/15/04BY: DAVID See Instructions on Reverse Side

(8/90)

* Surface casing cemented to surface

COPY SENT TO OPERATOR

Date: 7-16-04Initials: CHD

DIVISION OF OIL, GAS AND MINING**SPUDDING INFORMATION**Name of Company: WESTPORT OIL & GAS COMPANY LPWell Name: CIGE 296Api No: 43-047-34858 Lease Type: STATESection 14 Township 10S Range 22E County UINTAHDrilling Contractor PETE MARTIN RIG # BUCKET**SPUDDED:**Date 06/28/04Time 8:00 AMHow DRY**Drilling will commence:** _____Reported by JIM MURRAYTelephone # 1-435-828-1730Date 06/28/2004 Signed CHD

012

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING
ENTITY ACTION FORM - FORM 6

OPERATOR WESTPORT O&G COMPANY L.P.
ADDRESS 1368 SOUTH 1200 EAST
VERNAL, UTAH 84078

OPERATOR ACCT. NO. N 2115

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		
	99999		43-047-35402	NBU 921-33H	SENE	33	9S	21E	UINTAH	6/11/2004	

WELL 1 COMMENTS:

MIRU PETE MARTIN BUCKET RIG

SPUD WELL LOCATION ON 6/11/04 AT 2100 HRS.

Duplicate from 6/14/04

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		
B	99999	2900	43-047-35198	NBU 921-20N	SESW	20	9S	21E	UINTAH	6/24/2004	

WELL 2 COMMENTS:

MIRU PETE MARTIN BUCKET RIG

SPUD WELL LOCATION ON 6/24/04 AT 0600 HRS.

MURD

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		
B	99999	2900	43-047-34858	CIGE 296	NWNW	14	10S	22E	UINTAH	6/28/2004	

WELL 3 COMMENTS:

MIRU PETE MARTIN BUCKET RIG

SPUD WELL LOCATION ON 6/28/04 AT 8 AM

MURD

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		
B	99999	2900	43-047-35317	NBU 1022-4K	NESW	4	10S	22E	UINTAH	6/25/2004	

WELL 4 COMMENTS:

MIRU PETE MARTIN BUCKET RIG

SPUD WELL LOCATION ON 6/25/04 AT 1400 HRS.

MURD

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		

WELL 5 COMMENTS:

ACTION CODES (See instructions on back of form)

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another exit
- D - Re-assign well from one existing entity to a new entity
- E - Other (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected.

(3/89)

Post-It® Fax Note	7671	Date	# of pages
To	Eddene Russell	From	Shate Lyphage
Co./Dept.	UTALOGSM	Co./Dept.	Westport O&G CO. L.P.
Phone #	(801) 538-5330	Phone #	(435) 781-7024
Fax #	(801) 351-3940	Fax #	(435) 781-7094

Shate Lyphage
Signature

REGULATORY ANALYST 06/29/04
Title Date

Phone No. (435) 781-7024

RECEIVED

JUN 29 2004

DIV. OF OIL, GAS & MINING

P. 01

FAX NO. 4357817094

JUN-29-2004 TUE 03:09 PM EL PASO PRODUCTION

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

013

SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells. Use APPLICATION FOR PERMIT -- for such proposals		6. Lease Designation and Serial Number U-01197-A-ST
		7. Indian Allottee or Tribe Name
		8. Unit or Communitization Agreement NATURAL BUTTES UNIT
1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other (specify)		9. Well Name and Number CIGE 296
2. Name of Operator WESTPORT OIL & GAS COMPANY L.P.		10. API Well Number 43-047-34858
3. Address of Operator 1368 SOUTH 1200 EAST VERNAL, UTAH 84078	4. Telephone Number (435) 781-7024	11. Field and Pool, or Wildcat NATURAL BUTTES
5. Location of Well Footage : 371'FNL & 1215'FWL County : UINTAH QQ, Sec, T., R., M : NWNW SECTION 14-T10S-R-22E State : UTAH		
12. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		

NOTICE OF INTENT
 (Submit in Duplicate)

<input type="checkbox"/> Abandonment	<input type="checkbox"/> New Construction
<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Pull or Alter Casing
<input type="checkbox"/> Change of Plans	<input type="checkbox"/> Recompletion
<input type="checkbox"/> Conversion to Injection	<input type="checkbox"/> Shoot or Acidize
<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Vent or Flare
<input type="checkbox"/> Multiple Completion	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Other _____	

Approximate Date Work Will Start _____

SUBSEQUENT REPORT
 (Submit Original Form Only)

<input type="checkbox"/> Abandonment *	<input type="checkbox"/> New Construction
<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Pull or Alter Casing
<input type="checkbox"/> Change of Plans	<input type="checkbox"/> Shoot or Acidize
<input type="checkbox"/> Conversion to Injection	<input type="checkbox"/> Vent or Flare
<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Other WELL SPUD	

 Date of Work Completion 6/28/04

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION AND LOG form.

* Must be accompanied by a cement verification report.

13. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

MIRU PETE MARTIN BUCKET RIG. DRILLED 20" CONDUCTOR HOLE TO 40'.
 RAN 14" CONDUCTOR PIPE. CMT W/20 SX READY MIX CMT.

SPUD WELL LOCATION ON 6/28/04 AT 8 AM.
 PROCEDURES.

14. I hereby certify that the foregoing is true and correct.

 Name & Signature SHEILA UPCHEGO  Title Regulatory Analyst Date 06/29/04

(State Use Only)

RECEIVED
JUL 06 2004

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

015

SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells. Use APPLICATION FOR PERMIT -- for such proposals		6. Lease Designation and Serial Number <p align="center">U-01197-A-ST</p>
		7. Indian Allottee or Tribe Name
		8. Unit or Communitization Agreement <p align="center">NATURAL BUTTES UNIT</p>
1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other (specify)		9. Well Name and Number <p align="center">CIGE 296</p>
2. Name of Operator WESTPORT OIL & GAS COMPANY L.P.		10. API Well Number <p align="center">43-047-34858</p>
3. Address of Operator 1368 SOUTH 1200 EAST VERNAL, UTAH 84078	4. Telephone Number (435) 781-7024	11. Field and Pool, or Wildcat <p align="center">NATURAL BUTTES</p>
5. Location of Well Footage : 371'FNL & 1215'FWL County : UINTAH QQ, Sec. T., R., M : NWNW SECTION 14-T10S-R-22E State : UTAH		


12. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
NOTICE OF INTENT (Submit in Duplicate)		SUBSEQUENT REPORT (Submit Original Form Only)	
<input type="checkbox"/> Abandonment <input type="checkbox"/> Casing Repair <input type="checkbox"/> Change of Plans <input type="checkbox"/> Conversion to Injection <input type="checkbox"/> Fracture Treat <input type="checkbox"/> Multiple Completion <input type="checkbox"/> Other _____	<input type="checkbox"/> New Construction <input type="checkbox"/> Pull or Alter Casing <input type="checkbox"/> Recompletion <input type="checkbox"/> Shoot or Acidize <input type="checkbox"/> Vent or Flare <input type="checkbox"/> Water Shut-Off	<input type="checkbox"/> Abandonment * <input type="checkbox"/> Casing Repair <input type="checkbox"/> Change of Plans <input type="checkbox"/> Conversion to Injection <input type="checkbox"/> Fracture Treat <input checked="" type="checkbox"/> Other SURFACE CSG SET	<input type="checkbox"/> New Construction <input type="checkbox"/> Pull or Alter Casing <input type="checkbox"/> Shoot or Acidize <input type="checkbox"/> Vent or Flare <input type="checkbox"/> Water Shut-Off
Approximate Date Work Will Start _____		Date of Work Completion <u>7/19/04</u> Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION AND LOG form. * Must be accompanied by a cement verification report.	

13. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

DRILLED 12 1/4" SURFACE HOLE TO 1950'. RAN 9 5/8" 32.3# H-40 STC CSG.
 MIX & PMP 40 BBLs GEL PRFFLUSH MIX & PMP 240 SX "G" 15.8# W/2% CACL
 PMP @5.7 50 PSI TOTAL SLURRY PMP 49.1 BLS DROP PLUG ON THE FLY,
 DISPLACED CMT W/148 BBLs WATER @7 BPM, BUMP PLUG W/60 PSI PRESS TO
 630 POI, BLEED OFF FLOATS HOLDING. NO RETURNS DURING JOB.
 MIX & PMP DWN ANNULUS 100 SX 15.8# G W/4% CACL NO RETURNS
 MIX & PMP DWN ANNULUS 100 SX 15.8# G W/4% CACL NO RETURNS
 MIX & PMP DWN ANNULUS 225 SX 15.8# G W/4% CACL NO RETURNS
 MIX & PMP DWN ANNULUS 235 SX 15.8# G W/4% CACL CMT TO SURFACE

RECEIVED
JUL 27 2004
 DIV. OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct

Name & Signature SHEILA UPCHEGO  Title Regulatory Analyst Date 07/20/04
 (State Use Only)

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

016**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells.
 Use APPLICATION FOR PERMIT -- for such proposals

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other (specify) _____		6. Lease Designation and Serial Number U-01197-A-ST
2. Name of Operator WESTPORT OIL & GAS COMPANY L.P.		7. Indian Allottee or Tribe Name
3. Address of Operator 1368 SOUTH 1200 EAST VERNAL, UTAH 84078		8. Unit or Communitization Agreement NATURAL BUTTES UNIT
4. Telephone Number (435) 781-7024		9. Well Name and Number CIGE 296
5. Location of Well Footage : 371'FNL & 1215'FWL County : UINTAH QQ, Sec. T., R., M : NWNW SECTION 14-T10S-R-22E State : UTAH		10. API Well Number 43-047-34858
11. Field and Pool, or Wildcat NATURAL BUTTES		

12. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**NOTICE OF INTENT**

(Submit in Duplicate)

<input type="checkbox"/> Abandonment	<input type="checkbox"/> New Construction
<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Pull or Alter Casing
<input type="checkbox"/> Change of Plans	<input type="checkbox"/> Recompletion
<input type="checkbox"/> Conversion to Injection	<input type="checkbox"/> Shoot or Acidize
<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Vent or Flare
<input type="checkbox"/> Multiple Completion	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Other _____	

Approximate Date Work Will Start _____

SUBSEQUENT REPORT

(Submit Original Form Only)

<input type="checkbox"/> Abandonment *	<input type="checkbox"/> New Construction
<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Pull or Alter Casing
<input type="checkbox"/> Change of Plans	<input type="checkbox"/> Shoot or Acidize
<input type="checkbox"/> Conversion to Injection	<input type="checkbox"/> Vent or Flare
<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Other DRILLING OPERATIONS	

Date of Work Completion 8/17/04

Report results of Multiple Completions and Recompletions to different reservoirs
 on WELL COMPLETION OR RECOMPLETION AND LOG form.

* Must be accompanied by a cement verification report.

13. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

FINISHED DRILLING FROM 1950' TO 8440'. RAN 4 1/2" 11.6# I-80 CSG.
 LEAD CMT W/325 SX PREM LITE II @11.0 PPG 3.38 YIELD TAILED W/1100 50/50 POZ
 @14.3 PPG 1.31 YIELD. FLOATS HOLDING. GOOD RETURNS THROUGHOUT JOB

RELEASED CAZA 81 ON 8/17/04 AT 0000 HRS.

RECEIVED**AUG 30 2004**

DIV. OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct.

Name & Signature SHEILA UPCHEGO  Title Regulatory Analyst Date 08/17/04

(State Use Only)

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

017

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.


1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: U-01197-A-ST
2. NAME OF OPERATOR: WESTPORT OIL & GAS COMPANY L.P.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: NATURAL BUTTES UNIT
3. ADDRESS OF OPERATOR: 1368 SOUTH 1200 EAST CITY VERNAL STATE UT ZIP 84078		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES UNIT
4. LOCATION OF WELL FOOTAGES AT SURFACE: 371'FNL & 1215'FWL		8. WELL NAME and NUMBER: CIGE 296
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NWNW 14 10S 22E		9. API NUMBER: 4304734858
COUNTY: UINTAH		10. FIELD AND POOL, OR WILDCAT: NATURAL BUTTES
STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: 10/25/2004	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input checked="" type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

THE SUBJECT WELL LOCATION WAS PLACED ON PRODUCTION ON 10/25/04 AT 10:30 AM.

PLEASE REFER TO THE ATTACHED CHRONOLOGICAL WELL HISTORY.

NAME (PLEASE PRINT) SHEILA UPCHEGO	TITLE REGULATORY ANALYST
SIGNATURE 	DATE 10/28/2004

(This space for State use only)

RECEIVED

NOV 02 2004

DIV. OF OIL, GAS & MINING

WESTPORT OIL & GAS COMPANY, LP

CHRONOLOGICAL HISTORY

CIGE 296

UINTAH COUNTY, UT

DRILLING REPORT:

	SPUD	Surface Casing	Activity	Status
5/19/03			Start Building Loc. 5/19/03	Caza 7
5/20/03			Start Building Loc. 5/19/03	Caza 7
5/21/03			Start Building Loc. 5/19/03	Caza 7
5/22/03			Building Location. 25%	Caza 7
5/23/03			Building Loc. 35%	Caza 7
5/27/03			Building Loc. 50%	Caza 7
5/28/03			Building Location. 90%	Caza 7
5/29/03			Building Location. 100%	Caza 7
5/30/03			Building Location. 100%	Caza 7
6/2/03			Building Location. 100%	Caza 7
6/3/03			Building Location 100%	Caza 7
6/4/03			Building location 100%	Caza 7
6/5/03			Building location 100%	Caza 7
6/6/03			Building Location 100%	Caza 7
6/9/03			Building Location 100%	Caza 7
6/10/03			Building Location 100%	Caza 7
6/11/03			Building Location 100%	Caza 7
6/12/03			Building Location 100%	Caza 7
6/13/03			Building Location 100%	Caza 7
6/16/03			Building Location 100%	Caza 7

6/17/03		Building Location 100%	Caza 7
6/18/03		Building Location 100%	Caza 83 or 61
6/19/03	Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
6/20/03	Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
6/23/03	Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
6/24/03	Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
6/25/03	Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
6/26/03	Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
6/27/03	Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61

	SPUD	Surface Casing	Activity	Status
6/30/03		Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
7/1/03		Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
7/2/03		Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
7/3/03		Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
7/7/03		Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
7/8/03		Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
7/9/03		Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
7/10/03		Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
7/11/03		Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
7/14/03		Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
7/15/03		Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
7/16/03		Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
7/17/03		Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
7/18/03		Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
7/21/03		Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
7/22/03		Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
7/23/03		Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
7/24/03		Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61

7/25/03	Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
7/28/03	Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
7/29/03	Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
7/30/03	Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
7/31/03	Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
8/1/03	Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
8/4/03	Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
8/5/03	Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
8/6/03	Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
8/7/03	Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
8/8/03	Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
8/11/03	Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
8/12/03	Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
8/13/03	Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
8/14/03	Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
8/15/03	Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
8/18/03	Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
8/19/03	Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
8/20/03	Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
8/21/03	Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
8/22/03	Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
8/25/03	Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
8/26/03	Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
8/27/03	Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
8/28/03	Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
8/29/03	Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
9/2/03	Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61

9/3/03	Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
9/4/03	Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
9/5/03	Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
9/8/03	Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
9/9/03	Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
9/10/03	Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
9/11/03	Deep Test	Archies Bench,WO Air Rig	Caza 83 or 61
9/12/03	Deep Test	Archies Bench	Caza 83 or 61
9/15/03	Deep Test	Archies Bench	Caza 83 or 61
9/16/03	Deep Test	Archies Bench	Caza 83 or 61
9/17/03	Deep Test	Archies Bench	Caza 83 or 61
9/18/03	Deep Test	Archies Bench	Caza 83 or 61
9/19/03	Deep Test	Archies Bench	Caza 83 or
9/22/03	Deep Test	Archies Bench	Caza 83 or 61
9/23/03	Deep Test	Archies Bench	Caza 83 or 61
9/24/03	Deep Test	Archies Bench	Caza 83 or 61
9/25/03	Deep Test	Archies Bench	Caza 83 or 61
9/26/03	Deep Test	Archies Bench	Caza 83 or 61
9/29/03	Deep Test	Archies Bench	Caza 83 or 61
9/30/03	Deep Test	Archies Bench	Caza 83 or 61
10/1/03	Deep Test	Archies Bench	Caza 83 or 61
10/2/03	Deep Test	Archies Bench	Caza 83 or 61
10/3/03	Deep Test	Archies Bench	Caza 83 or 61
10/6/03	Deep Test	Archies Bench	Caza 83 or 61
10/7/03	Deep Test	Archies Bench	Caza 83 or 61
10/8/03	Deep Test	Archies Bench	Caza 83 or 61
10/9/03	Deep Test	Archies Bench	Caza 83 or 61
10/10/03	Deep Test	Archies Bench	Caza 83 or 61

10/13/03	Deep Test	Archies Bench	Caza 83 or 61
10/14/03		Build Location, 100% complete	
10/15/03		Build Location, 100% complete	
10/16/03		Build Location, 100% complete	
10/17/03		Location Complete	(DeepTest Archie Bench)
10/20/03		Location Complete	(DeepTest Archie Bench)
10/21/03		Location Complete	(DeepTest Archie Bench)
10/22/03		Location Complete	(DeepTest Archie Bench)
10/23/03		Location Complete	(DeepTest Archie Bench)
10/24/03		Location Complete	(DeepTest Archie Bench)
10/27/03		Location Complete	(DeepTest Archie Bench)
10/28/03		Location Complete	(DeepTest Archie Bench)
10/29/03		Location Complete	(DeepTest Archie Bench)
10/30/03		Location Complete	(DeepTest Archie Bench)
10/31/03		Location Complete	(DeepTest Archie Bench)
11/3/03		Location Complete	(DeepTest Archie Bench)
11/4/03		Location Complete	(DeepTest Archie Bench)
11/5/03		Location Complete	(DeepTest Archie Bench)
11/6/03		Location Complete	(DeepTest Archie Bench)
11/7/03		Location Complete	(DeepTest Archie Bench)
11/10/03		Location Complete	(DeepTest Archie Bench)
11/11/03		Location Complete	(DeepTest Archie Bench)
11/12/03		Location Complete	(DeepTest Archie Bench)
11/13/03		Location Complete	(DeepTest Archie Bench)
11/14/03		Location Complete	(DeepTest Archie Bench)
11/17/03		Location Complete	(DeepTest Archie Bench)
11/18/03		Location Complete	(DeepTest Archie Bench)

11/19/03	Location Complete	(DeepTest Archie Bench)
11/20/03	Location Complete	(DeepTest Archie Bench)
11/21/03	Location Complete	(DeepTest Archie Bench)
11/24/03	Location Complete	(DeepTest Archie Bench)
11/25/03	Location Complete	(DeepTest Archie Bench)
11/26/03	Location Complete	(DeepTest Archie Bench)
12/1/03	Location Complete	(DeepTest Archie Bench)
12/2/03	Location Complete	(DeepTest Archie Bench)
12/3/03	Location Complete	(DeepTest Archie Bench)
12/4/03	Location Complete	(DeepTest Archie Bench)
12/5/03	Location Complete	(DeepTest Archie Bench)
12/8/03	Location Complete	(DeepTest Archie Bench)
12/9/03	Location Complete	(DeepTest Archie Bench)
12/10/03	Location Complete	(DeepTest Archie Bench)
12/11/03	Location Complete	(DeepTest Archie Bench)
12/12/03	Location Complete	(DeepTest Archie Bench)
12/15/03	Location Complete	(DeepTest Archie Bench)
12/16/03	Location Complete	(DeepTest Archie Bench)
12/17/03	Location Complete	(DeepTest Archie Bench)
12/18/03	Location Complete	(DeepTest Archie Bench)
12/19/03	Location Complete	(DeepTest Archie Bench)
12/20/03	Location Complete	(DeepTest Archie Bench)
12/22/03	Location Complete	(DeepTest Archie Bench)
12/23/03	Location Complete	(DeepTest Archie Bench)
12/29/03	Location Complete	(DeepTest Archie Bench)
12/30/03	Location Complete	(DeepTest Archie Bench)
1/2/04	Location Complete	(DeepTest Archie Bench)
1/5/04	Location Complete	(DeepTest Archie Bench)

1/6/04	Location Complete	(DeepTest Archie Bench)
1/7/04	Location Complete	Caza 82
1/8/04	Location Complete	Caza 82
1/9/04	Location Complete	Caza 82
1/12/04	Location Complete	Caza 82
1/13/04	Location Complete	Caza 82
1/14/04	Location Complete	Caza 82
1/15/04	Location Complete	Caza 82
1/16/04	Location Complete	Caza 82
1/19/04	Location Complete	Caza 82
1/20/04	Location Complete	Caza 82
1/21/04	Location Complete	Caza 82
1/22/04	Location Complete	Caza 82
1/23/04	Location Complete	Caza 82
1/26/04	Location Complete	Caza 82
1/27/04	Location Complete	Caza 82
1/28/04	Location Complete	Caza 82
1/29/04	Location Complete	Caza 82
1/30/04	Location Complete	Caza 82
2/2/04	Location Complete	Caza 82
2/3/04	Location Complete	Caza 82
2/4/04	Location Complete	Caza 82
2/5/04	Location Complete	Caza 82
2/6/04	Location Complete	Caza 82
2/9/04	Location Complete	Caza 82
2/10/04	Location Complete	Caza 82
2/11/04	Location Complete	Caza 82

2/12/04	Location Complete	Caza 82
2/13/04	Location Complete	Caza 82
2/16/04	Location Complete	Caza 82
2/17/04	Location Complete	Caza 82
2/18/04	Location Complete	Caza 82
2/19/04	Location Complete	Caza 82
2/20/04	Location Complete	Caza 82
2/23/04	Location Complete	Caza 82
2/24/04	Location Complete	Caza 82
2/25/04	Location Complete	Caza 82
2/26/04	Location Complete	Caza 82
2/27/04	Location Complete	Caza 82
3/1/04	Location Complete	Caza 82
3/2/04	Location Complete	Caza 82
3/3/04	Location Complete	Caza 82
3/4/04	Location Complete	Caza 82
3/5/04	Location Complete	Caza 82
3/8/04	Location Complete	Caza 82
3/9/04	Location Complete	Caza 82
3/10/04	Location Complete	Caza 82
3/11/04	Location Complete	Caza 82
3/12/04	Location Complete	Caza 82
3/15/04	Location Complete, Archies B	Caza 81
3/16/04	Location Complete, Archies B	Caza 81
3/17/04	Location Complete, Archies B	Caza 81
3/18/04	Location Complete, Archies B	Caza 81
3/19/04	Location Complete, Archies B	Caza 81
3/22/04	Location Complete, Archies B	Caza 81

3/23/04	Location Complete, Archies B	Caza 81
3/24/04	Location Complete, Archies B	Caza 81
3/25/04	Location Complete, Archies B	Caza 81
3/26/04	Location Complete, Archies B	Caza 81
3/29/04	Location Complete, Archies B	Caza 81
3/30/04	Location Complete, Archies B	Caza 81
3/31/04	Location Complete, Archies B	Caza 81
4/1/04	Location Complete, Archies B	Caza 81
4/2/04	Location Complete, Archies B	Caza 81
4/5/04	Location Complete, Archies B	Caza 81
4/6/04	Location Complete, Archies B	Caza 81
4/7/04	Location Complete, Archies B	Caza 81
4/8/04	Location Complete, Archies B	Caza 81
4/12/04	Location Complete, Archies B	Caza 81
4/13/04	Location Complete, Archies B	Caza 81
4/14/04	Location Complete, Archies B	Caza 81
4/15/04	Location Complete, Archies B	Caza 81
4/16/04	Location Complete, Archies B	Caza 81
4/19/04	Location Complete, Archies B	Caza 81
4/20/04	Location Complete, Archies B	Caza 81
4/21/04	Location Complete, Archies B	Caza 81
4/22/04	Location Complete, Archies B	Caza 81
4/23/04	Location Complete, Archies B	Caza 81
4/26/04	Location Complete, Archies B	Caza 81
4/27/04	Location Complete, Archies B	Caza 81
4/28/04	Location Complete, Archies B	Caza 81
4/29/04	Location Complete, Archies B	Caza 81

4/30/04	Location Complete, Archies B	Caza 81
5/3/04	Location Complete, Archies B	Caza 81
5/4/04	Location Complete, Archies B	Caza 81
5/5/04	Location Complete, Archies B	Caza 81
5/6/04	Location Complete, Archies B	Caza 81
5/7/04	Location Complete, Archies B	Caza 81
5/10/04	Location Complete, Archies B	Caza 81
5/11/04	Location Complete, Archies B	Caza 81
5/12/04	Location Complete, Archies B	Caza 81
5/13/04	Location Complete, Archies B	Caza 81
5/14/04	Location Complete, Archies B	Caza 81
5/17/04	Location Complete, Archies B	Caza 8
5/18/04	Location Complete, Archies B	Caza 81
5/19/04	Location Complete, Archies B	Caza 81
5/20/04	Location Complete, Archies B	Caza 81
5/21/04	Location Complete, Archies B	Caza 81
5/24/04	Location Complete, Archies B	Caza 81
5/25/04	Location Complete, Archies B	Caza 81
5/26/04	Location Complete, Archies B	Caza 81
5/27/04	Location Complete, Archies B	Caza 81
5/28/04	Location Complete, Archies B	Caza 81
5/31/04	Location Complete, Archies B	Caza 81
6/1/04	Location Complete, Archies B	Caza 81
6/2/04	Location Complete, Archies B	Caza 81
6/3/04	Location Complete, Archies B	Caza 81
6/4/04	Location Complete, Archies B	Caza 81
6/7/04	Location Complete, Archies B	Caza 81
6/8/04	Location Complete, Archies B	Caza 81

6/9/04		Location Complete, Archies B	Caza 81
6/10/04		Location Complete, Archies B	Caza 81
6/11/04		Location Complete, Archies B	Caza 81
6/14/04		Location Complete, Archies B	Caza 81
6/15/04		Location Complete, Archies B	Caza 81
6/16/04		Location Complete, Archies B	Caza 81
6/17/04		Location Complete, Archies B	Caza 81
6/18/04		Location Complete, Archies B	Caza 81
6/21/04		Location Complete, Archies B	Caza 81
6/22/04		Location Built, WOBR	Caza 81
6/23/04		Location Built, WOBR	Caza 81
6/24/04		Location Built, WOBR	Caza 81
6/25/04		Location Built, WOBR	Caza 81
6/28/04		Location Built, WOBR	Caza 81
6/29/04	14" @ 40'	Location Built, WOAR	Caza 81
6/30/04	14" @ 40'	Location Built, WOAR	Caza 81
7/1/04	14" @ 40'	Location Built, WOAR	Caza 81
7/2/04	14" @ 40'	Location Built, WOAR	Caza 81
7/6/04	14" @ 40'	Location Built, WOAR	Caza 81
7/7/04	14" @ 40'	Location Built, WOAR	Caza 81
7/8/04	14" @ 40'	Location Built, WOAR	Caza 81
7/9/04	14" @ 40'	Location Built, WOAR	Caza 81
7/12/04	14" @ 40'	Location Built, WOAR	Caza 81
7/13/04	14" @ 40'	Location Built, WOAR	Caza 81
7/14/04	14" @ 40'	Location Built, WOAR	Caza 81
7/15/04	14" @ 40'	Location Built, WOAR	Caza 81
7/16/04	7/16/04 14" @ 40'	Spud surface hole w/Air Rig. DA	Caza 81

7/19/04	7/16/04	9 5/8" @ 1924'	Drlg to 1950'. Set 9 5/8" csg	WORT Caza 81
7/20/04	7/16/04	9 5/8" @ 1924'	Drlg to 1950'. Set 9 5/8" csg	WORT Caza 81
7/21/04	7/16/04	9 5/8" @ 1924'	Drlg to 1950'. Set 9 5/8" csg	WORT Caza 81
7/22/04	7/16/04	9 5/8" @ 1924'	Archies Bench.	WORT Caza 81
7/23/04	7/16/04	9 5/8" @ 1924'	Archies Bench.	WORT Caza 81
7/26/04	7/16/04	9 5/8" @ 1924'	Archies Bench.	WORT Caza 81
7/27/04	7/16/04	9 5/8" @ 1924'	Archies Bench.	WORT Caza 81
7/28/04	7/16/04	9 5/8" @ 1924'	Archies Bench.	WORT Caza 81
7/29/04	7/16/04	9 5/8" @ 1924'	Archies Bench.	WORT Caza 81
7/30/04	7/16/04	9 5/8" @ 1924'	Archies Bench.	WORT Caza 81
8/2/04	7/16/04	9 5/8" @ 1924'	Archies Bench.	WORT Caza 81
8/3/04	7/16/04	9 5/8" @ 1924'	Archies Bench.	WORT Caza 81
8/4/04	7/16/04	9 5/8" @ 1924'	Archies Bench.	WORT Caza 81
8/5/04	7/16/04	9 5/8" @ 1924'	Archies Bench.	WORT Caza 81

8/6/04

TD: 1950' Csg. 9 5/8" @ 1924' MW: 8.4 SD:8/X/04 DSS: 0
MIRU Caza 81 on Archie's Bench, CIGE 296. Raise derrick. Rig up rotary tools.

8/9/04

TD: 5930' Csg. 9 5/8" @ 1924' MW: 8.5 SD:8/7/04 DSS: 3
Finish rigging up rotary tools. NU and test BOPE. PU PDC bit and mud motor. Drill cement and FE. Rotary spud 7 7/8" hole @ 0200 hrs 8/7/04. Drill and survey from 1950'-5930'. DA @ report time. Top of Wasatch @ 4125'.

8/10/04

TD: 6823' Csg. 9 5/8" @ 1924' MW: 9.2 SD:8/7/04 DSS: 4
Drill and survey from 5930'-6823'. DA @ report time. Top of Mesaverde @ 6336'.

8/11/04

TD: 7565' Csg. 9 5/8" @ 1924' MW: 9.6 SD:8/7/04 DSS: 5
Drill and survey from 6823'-7565'. CCH and weight up system @ report time.

8/12/04

TD: 7604' Csg. 9 5/8" @ 1924' MW: 9.6 SD:8/7/04 DSS: 6
CCH and weight up system. POOH to 4738'. Pulled tight. Work through tight hole. FOOH and change out mud motor. TIH to 4809'. Ream through bridge from 4809'-4873' and 4905'-4969'. FIH. Drill from 7565'-7604'. DA @ report time.

8/13/04

TD: 7896' Csg. 9 5/8" @ 1924' MW: 9.8 SD:8/7/04 DSS: 7
Drill from 7604'-7896'. DA @ report time.

8/16/04 TD: 8440' Csg. 9 5/8" @ 1924' MW: 10.1 SD:8/7/04 DSS: 10
 Drill from 7896'-8440' TD. CCH for logs. Run Triple Combo. CCH for casing. Lay down
 drill string. RU and run 4 1/2" Production Casing @ report time.

8/17/04 TD: 8440' Csg. 9 5/8" @ 1924' MW: 10.1 SD:8/7/04 DSS: 11
 Run and cement 4 1/2" Production Casing. Set slips. ND BOPE and clean pits. Release rig @
 2400 hrs 8/16/04. Rig down rotary tools. Will move to NBU 1022-23K this am.

10/15/04 PROG: 7:00 AM. HELD SAFETY MEETING. ROAD RIG & EQUIP F/NBU 1022-23F TO
 LOC. MIRU. SPOT EQUIP. NDWH. NUBOP'S. TALLY & PREP 270 JTS 2-3/8" J-55 TBG.
 PU 3-7/8" SMITH BIT. BIT SUB & RIH. TAG PBTB @ 8390', (44' RAT HOLE). RU PMP &
 LINES. CIRC WL CLEAN W/130 BBLs 2% KCL. POOH LD 30 JTS 2-3/8" TBG ON
 TRAILER. SWI. SDFN.

10/18/04 PROG: 7:00 AM. HELD SAFETY MEETING. CONT TO POOH W/TBG F/7580'. LD BHA.
 MIRU CUTTERS. PU CBL/CCL/GR LOG TOOLS & RIH. TAG PBTB. LOG WL F/8395' TO
 SURF. POOH. LD LOG TOOLS. PU 3-3/8" PROSPECTOR PERF GUNS LOADED W/23 GM
 CHARGES. 4 SPF, 90 DEG PHASING & RIH. SHOOT 24 HOLES F/8340' - 46', PU SHOOT 16
 HOLES F/8263' - 67'. POOH. RDMO CUTTERS. X/O INSTALL DBL BLIND RAMS. PREP
 TO FRAC MONDAY AM. SWI. SDFWE.

10/19/04 PROG: FRAC STGS 1-5 PER DESIGN.

10/20/04 PROG: HELD SAFETY MEETING. OPEN UP WL, RU CWLS, PU 10K CBP & 3-3/8" GUN.
 RIH SET PLUG 6970', PUH PERF 6936 - 6944' 4 SPF, TOTAL OF 32 HOLES. POOH LD WL
 TLS.

STAGE 6: BRK @ 3559#, ISIP: 2472#, FG: 0.79, POC: 94%. EST RATE: 52 BPM @ 5550#.
 FRAC STAGE AS PER DESIGN W/YF118ST+ GEL. START PROP NET @ 123K LBS SD (4
 SX). TOT SD: 144,000 LBS. TOT FL: 1111BBL, ISIP: 2709#, FG: 0.83, NPI: 237. MR: 53
 BPM, MP: 5855#, AR: 47.9 BPM, AP: 4684#. RU CWLS. PU 10K CBP & 3-3/8" PERF GUN.
 RIH, SET PLUG @ 6640', PUH PERF 6600 - 6608' 4 SPF & 6418 - 6424' 4 SPF, TOT OF 56
 HOLES. POOH, LD WL TLS.

STAGE 7: BRK @ 2579#, ISIP: 1590, FG: 0.68, POC: 82%. EST RATE: 50.7 BPM @ 3880#.
 FRAC STAGE AS PER DESIGN W/YF118ST+ GEL. INITIATE PROP NET @ 195K LBS SD
 (6 SX). TOT SD: 242,000 LBS SD, TOT FL: 1724 BBL, ISIP: 2124#, FG: 0.76. MR: 51.1 BPM,
 MP: 4054#, AR: 48.1 BPM, AP: 3637#. RDMO D/S. RU CWLS, PU 5K KILL PLUG, RIH SET
 PLUG @ 6350', POOH LD TLS & LUB, RDMO CWLS. RU TBG EQUIP. PU 3-7/8" ROCK
 BIT & POBS & 1 JT 2-3/8" TBG. RIH W/BIT, SUB & TBG, TAG FILL @ 6340'. LD 1 JT. RU
 PWR SWIVEL EQUIP. SWI, PREP TO DRL IN MORN. SDFN.

10/21/04 PROG: 7:00 AM. HELD SAFETY MEETING, PU 1 JT TBG. BRK CONV CIRC W/2% KCL &
 BEG TO DRL.

DRL UP 1ST CBP @ 6350' IN 10 MIN. (100# INC). CONT TO RIH. TAG FILL @ 6600', (40'
 FILL). CO TO 2ND CBP @ 6640'.

DRL UP 2ND CBP IN 15 MIN. (100# INC). CONT TO RIH. TAG FILL @ 6940' (30' FILL). CO
 TO 3RD CBP @ 6970'.

DRL UP 3RD CBP IN 10 MIN. (200# INC). CONT TO RIH. TAG FILL @ 7160'. (60' FILL). CO
 TO 4TH CBP @ 7220'.

DRL UP 4TH CBP IN 13 MIN. (500# INC). CONT TO RIH. TAG FILL @ 7500', (30' FILL). CO

TO 5TH CBP @ 7530'.

DRL UP 5TH CBP IN 10 MIN. (400# INC). CONT TO RIH. TAG FILL @ 7850', (50' FILL). CO TO 6TH CBP @ 7900'

DRL UP 6TH CBP IN 8 MIN. (700# INC). CONT TO RIH. TAG FILL @ 8110'. (60' FILL). CO TO 7TH CBP @ 8170'.

DRL UP 7TH CBP IN 10 MIN. (700# INC). CONT TO RIH. TAG FILL @ 8360' (30' FILL). CO TO PBTD @ 8390'.

CIRC WL CLEAN. RD DRL EQUIP. POOH. LD 12 JTS TBG ON TRAILER. LUBRICATE TBG HANGER INTO WL. LAND TBG W/EOT @ 8009'. NDBOP. NUWH. RU PMP & LINES. PMP OFF THE BIT SUB @ 2700#. RU FLOWBACK LINES. RACK OUT EQUIP. (TO WINDY TO RIG DN). TURN OVER TO FLOWBACK CREW @ 3:00 P.M.

FTP: #50, SICP: #1100, OPEN CHK

10/22/04 PROG: WELL ON FLOWBACK, FLOWBACK REPORT: CP: 1000#, TP: 1225#, 20/64 CHK, 40 BWPH, 17 HRS, SD: TRACE, TTL BBLS FLWD: 2626, TODAY'S LTR: 8579 BBLS, LOAD REC TODAY: 2,626 BBLS, REMAINING LTR: 5,953 BBLS, TOTAL LOAD REC TO DATE: 2,626 BBLS.

10/25/04 PROG: WELL ON FLOWBACK, FLOWBACK REPORT: CP: 2400#, TP: 1500#, 18/64 CHK, 20 BWPH, 24 HRS, SD: CLEAN, TTL BBLS FLWD: 494, TODAY'S LTR: 3,595 BBLS, LOAD REC TODAY: 494 BBLS, REMAINING LTR: 3,101 BBLS, TOTAL LOAD REC TO DATE: 5,478 BBLS.

10/26/04 PROG: WELL WENT ON SALES. 10/25/04, 10:30 AM. 1,500 MCF, 20/64 CHK, SICP: 1,600#, FTP: 1,300#, 35 BWPH, FINAL REPORT FOR COMPLETION.

10/27/04 **ON SALES**
10/25/04: 743 MCF, 0 BC, 800 BW, TP: 1230#, CP: 2150#, 20/64 CHK, 17 HRS, LP: 362#.

10/28/04 **ON SALES**
10/26/04: 1523 MCF, 0 BC, 750 BW, TP: 1103#, CP: 1939#, 20/64 CHK, 24 HRS, LP: 390#.

018

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

5. LEASE DESIGNATION AND SERIAL NO.

U-01197-A-ST

WELL COMPLETION OR RECOMPLETION REPORT AND LOG*

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

1a. TYPE OF WELL

OIL
WELL ☐GAS
WELL ☒DRY ☐

Other _____

1b. TYPE OF COMPLETION

NEW
WELL ☒WORK
OVER ☐DEEP-
EN ☐PLUG
BACK ☐DIFF.
RESVR. ☐

Other _____

7. UNIT AGREEMENT NAME

NATURAL BUTTES UNIT

8. FARM OR LEASE NAME, WELL NO.

CIGE

2. NAME OF OPERATOR

WESTPORT OIL & GAS COMPANY L.P.

9. WELL NO.

296

3. ADDRESS AND TELEPHONE NO.

1368 SOUTH 1200 EAST VERNAL, UTAH 84078

(435) 781-7024

10. FIELD AND POOL OR WILDCAT

NATURAL BUTTES

4. LOCATION OF WELL (Report locations clearly and in accordance with any State requirements)

At Surface

NWNW 371'FNL & 1215'FWL

11. SEC., T., R., M., OR BLOCK AND SURVEY

OR AREA

SECTION 14-110S-R22E

At total depth

14. API NO.

43-047-34858

DATE ISSUED

4/8/03

12. COUNTY

UINTAH

13. STATE

UTAH

15. DATE SPUDDED

6/28/04

16. DATE T.D. REACHED

8/16/04

17. DATE COMPL. (Ready to prod. or Plug &)

10/25/04

18. ELEVATIONS (DF, RKB, RT, GR, ETC.)*

5183'GL

19. ELEV. CASINGHEAD

20. TOTAL DEPTH, MD & TVD

8440' MD

TVD

21. PLUG, BACK T.D., MD & TVD

8390' TD

MD

TVD

22. IF MULTIPLE COMPL.,

HOW MANY

23. INTERVALS ROTARY TOOLS

DRILLED BY

----->

X

CABLE TOOLS

24. PRODUCING INTERVAL(S), OF THIS COMPLETION--TOP, BOTTOM, NAME (MD AND TVD)

MESAVERDE: 6418'-8346'

RECEIVED

26. TYPE ELECTRIC AND OTHER LOGS RUN

CBL-CCL-GR

27. WAS WELL CORED YES ☐ NO ☒ (Submit analysis)DRILL STEM TEST YES ☐ NO ☒ (See reverse side)

NOV 24 2004

23. CASING RECORD (Report all strings set in well)

CASING SIZE	WEIGHT, LB./FT.	DEPTH SET (MD)	HOLE SIZE	CEMENTING RECORD
14" CONDUCTOR	50#	40'	20"	20 SX
9 5/8"	32.3#	1950'	12 1/4"	900 SX
4 1/2"	11.6#	8440'	7 7/8"	1425 SX

29. LINER RECORD

SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT*	SCREEN (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
					2 3/8"	8010'	

31. PERFORATION RECORD (Interval, size and number)

INTERVAL SIZE NUMBER
6418'-8346' 0.35 316 HOLES

32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL (MD)	AMOUNT AND KIND OF MATERIAL USED
6418'-8346'	PMP 8805 BBLs YF118ST & 1,358,000#
	20/40 OTTOWA SD

33.* PRODUCTION

DATE FIRST PRODUCTION 10/25/04		PRODUCTION METHOD (Flowing, gas lift, pumping--size and type of pump) FLOWS FROM WELL					WELL STATUS (Producing or shut-in) PRODUCING GAS WELL	
DATE OF TEST 10/28/04	HOURS TESTED 24	CHOKE SIZE 20/64	PROD'N. FOR TEST PERIOD ----->	OIL--BBLs. 0	GAS--MCF. 1596	WATER--BBL. 565		GAS-OIL RATIO
FLOW. TUBING PRESS. 934#	CASING PRESSURE 1688#	CALCULATED 24-HOUR RATE ----->	OIL--BBL. 0	GAS--MCF. 1596	WATER--BBL. 565		OIL GRAVITY-API (CORR.)	
34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.) SOLD						TEST WITNESSED BY		

35. LIST OF ATTACHMENTS

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records

SIGNED SHEILA UPCHEGO

TITLE REGULATORY ANALYST

DATE 11/15/2004

See Spaces for Addition Data on Reverse Side

INSTRUCTIONS

This form should be completed in compliance with the Utah Oil and Gas Conservation General Rules. If not filed prior to this time, all logs, tests, and directional surveys as required by Utah Rules should be attached and submitted with this report.

ITEM 18: Indicate which elevation is used as reference for depth measurements given in other spaces on this form and on any attachments. ITEMS 22 and 24: If this well is completed for separate production from more than one interval zone (multiple completion), so state in item 22, and in item 24 show the producing interval, or intervals, top(s), bottom(s) and name(s) for only the interval reported in item 33. Submit a separate report (page) on this form, adequately identified, for each additional interval to be separately produced, showing the additional data pertinent to such interval.

ITEM 29: "Sacks Cement": Attached supplemental records for this well should show the details of any multiple stage cementing and the location of the cementing tool.

ITEM 33: Submit a separate completion report on this form for each interval to be separately produced (see instruction for items 22 and 24 above).

37. SUMMARY OF POROUS ZONES: Show all important zones of porosity and contents thereof; cored intervals; and all drill-stem, tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.				38. GEOLOGIC MARKERS		
Formation	Top	Bottom	Description, contents, etc.	Name	Meas. Depth	Top True Vert. Depth
WASATCH MESAVARDE	4110' 6391'	6391'				

Division of Oil, Gas and Mining
OPERATOR CHANGE WORKSHEET

ROUTING

1. DJJ

2. CDW

X Change of Operator (Well Sold)

Operator Name Change/Merger

The operator of the well(s) listed below has changed, effective:

1/6/2006

FROM: (Old Operator):

N2115-Westport Oil & Gas Co., LP
 1368 South 1200 East
 Vernal, UT 84078

Phone: 1-(435) 781-7024

TO: (New Operator):

N2995-Kerr-McGee Oil & Gas Onshore, LP
 1368 South 1200 East
 Vernal, UT 84078

Phone: 1-(435) 781-7024

CA No.

Unit:

NATURAL BUTTES UNIT

WELL NAME

SEC TWN RNG

API NO

ENTITY

NO

LEASE

TYPE

WELL

TYPE

WELL

STATUS

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

1. (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 5/10/2006
2. (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 5/10/2006
3. The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 3/7/2006
- 4a. Is the new operator registered in the State of Utah: YES Business Number: 1355743-0181
- 4b. If **NO**, the operator was contacted on: _____
- 5a. (R649-9-2)Waste Management Plan has been received on: IN PLACE
- 5b. Inspections of LA PA state/fee well sites complete on: n/a 3 LA wells & all PA wells transferred
- 5c. Reports current for Production/Disposition & Sundries on: ok
6. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM 3/27/2006 BIA not yet
7. **Federal and Indian Units:**
 The BLM or BIA has approved the successor of unit operator for wells listed on: 3/27/2006
8. **Federal and Indian Communization Agreements ("CA"):**
 The BLM or BIA has approved the operator for all wells listed within a CA on: n/a
9. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: _____

DATA ENTRY:

1. Changes entered in the **Oil and Gas Database** on: 5/15/2006
2. Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 5/15/2006
3. Bond information entered in RBDMS on: 5/15/2006
4. Fee/State wells attached to bond in RBDMS on: 5/16/2006
5. Injection Projects to new operator in RBDMS on: _____
6. Receipt of Acceptance of Drilling Procedures for APD/New on: n/a Name Change Only

BOND VERIFICATION:

1. Federal well(s) covered by Bond Number: CO1203
2. Indian well(s) covered by Bond Number: RLB0005239
3. (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number RLB0005236
- a. The **FORMER** operator has requested a release of liability from their bond on: n/a rider added KMG
- The Division sent response by letter on: _____

LEASE INTEREST OWNER NOTIFICATION:

4. (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: 5/16/2006

COMMENTS:

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

KERR-McGEE OIL & GAS ONSHORE LP

3a. Address

1368 SOUTH 1200 EAST VERNAL, UT 84078

3b. Phone No. (include area code)

(435) 781-7024

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SEE ATTACHED

5. Lease Serial No.

MULTIPLE LEASES

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

MUTIPLE WELLS

9. API Well No.

10. Field and Pool, or Exploratory Area

11. County or Parish, State

UINTAH COUNTY, UTAH

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other CHANGE OF OPERATOR
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

PLEASE BE ADVISED THAT KERR-McGEE OIL & GAS ONSHORE LP, IS CONSIDERED TO BE THE OPERATOR OF THE ATTACHED WELL LOCATIONS. EFFECTIVE JANUARY 6, 2006.

KERR-McGEE OIL & GAS ONSHORE LP, IS RESPONSIBLE UNDER TERMS AND CONDITIONS OF THE LEASE(S) FOR THE OPERATIONS CONDUCTED UPON LEASE LANDS. BOND COVERAGE IS PROVIDED BY STATE OF UTAH NATIONWIDE BOND NO. RLB0005237.

BLM BOND = C01203
BIA BOND = RLB0005239

APPROVED 5/16/06

Earlene Russell

Division of Oil, Gas and Mining
Earlene Russell, Engineering Technician

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

RANDY BAYNE

Signature

Title

DRILLING MANAGER

Date

May 9, 2006

THIS SPACE FOR FEDERAL OR STATE USE

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)

RECEIVED

MAY 10 2006

DIV. OF OIL, GAS & MINING

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

5. Lease Serial No.

MULTIPLE LEASES

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

MUTIPLE WELLS

9. API Well No.

10. Field and Pool, or Exploratory Area

11. County or Parish, State

UINTAH COUNTY, UTAH

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

WESTPORT OIL & GAS COMPANY L.P.

3a. Address

1368 SOUTH 1200 EAST VERNAL, UT 84078

3b. Phone No. (include area code)

(435) 781-7024

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SEE ATTACHED

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other CHANGE OF OPERATOR
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

EFFECTIVE JANUARY 6, 2006, WESTPORT OIL & GAS COMPANY L.P., HAS RELINQUISHED THE OPERATORSHIP OF THE ATTACHED WELL LOCATIONS TO KERR-McGEE OIL & GAS ONSHORE LP.

APPROVED 5/16/06
Earlene Russell
Division of Oil, Gas and Mining
Earlene Russell, Engineering Technician

RECEIVED
MAY 10 2006

DIV. OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

BRAD LANEY

Signature

Title

ENGINEERING SPECIALIST

Date

May 9, 2006

THIS SPACE FOR FEDERAL OR STATE USE

Approved by

Brad Laney

Title

Date

5-9-06

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.